



EROSION AND SEDIMENT CONTROL NOTES:

- ADDITIONAL EROSION AND SEDIMENT CONTROL MATERIALS (I.E. SILT FENCE, STRAW BALES, CLEAR STONES ETC.) ARE TO BE KEPT ON SITE FOR EMERGENCIES AND REPAIRS.
- EROSION AND SEDIMENT CONTROLS METHODS ARE TO BE CONTINUOUSLY EVALUATED; AND UPGRADES ARE TO BE IMPLEMENTED, WHEN NECESSARY.
- THE CONTRACTOR IS ULTIMATELY RESPONSIBLE FOR CONTROLLING SEDIMENT & EROSION WITHIN THE CONSTRUCTION SITE FOR THE TOTAL PERIOD OF THE CONSTRUCTION. THE SEDIMENT LADEN WATER WILL NOT BE ALLOWED TO DISCHARGE TO THE CREEK .
- AN AFTER HOURS CONTACT NUMBER IS TO BE VISIBLY POSTED ON-SITE FOR EMERGENCIES. ALL THE PLANS SHOULD HAVE NAME AND CONTACT INFO OF THE PERSON RESPONSIBLE FOR ESC MEASURES.
- ANY SEDIMENT SPILL FROM THE SITE MUST BE REPORTED TO MINISTRY OF ENVIRONMENT AND CLIMATE CHANGE (CALL SPILL ACTION CENTER AT 1-800-268-6060.)



EROSION & SEDIMENT CONTROL PLAN	
PART OF LOT 1 AND ALL OF LOT 2 AND THORNY-BRAE PLACE REGISTERED PLAN 498 AND PART OF LOTS 3 AND 4, RANGE 5 NORTH OF DUNDAS CITY OF MISSISSAUGA REGIONAL MUNICIPALITY OF PEEL	
DATE:	MAR 2019
PROJECT No.:	UD15-0682
SCALE:	1:750
FIGURE No.:	ESC-01