
Council

Date: June 17, 2020
Time: 9:30 AM
Location: Online Video Conference

Members

Mayor Bonnie Crombie	
Councillor Stephen Dasko	Ward 1
Councillor Karen Ras	Ward 2
Councillor Chris Fonseca	Ward 3
Councillor John Kovac	Ward 4
Councillor Carolyn Parrish	Ward 5
Councillor Ron Starr	Ward 6
Councillor Dipika Damerla	Ward 7
Councillor Matt Mahoney	Ward 8
Councillor Pat Saito	Ward 9
Councillor Sue McFadden	Ward 10
Councillor George Carlson	Ward 11

Due to efforts to contain the spread of COVID-19 and to protect all individuals, the Council Chamber will not be open to the public to attend Council and Committee meetings until further notice.

Deputations and Public Comments: Any member of the public interested in speaking to an item listed on the agenda may register at megan.piercey@mississauga.ca by Monday, June 15, 2020 before 4:00 PM. Comments submitted will be considered as public information and entered into public record.

Contact

Megan Piercey, Legislative Coordinator, Legislative Services
905-615-3200 ext. 4915
Email megan.piercey@mississauga.ca

Find it Online

<http://www.mississauga.ca/portal/cityhall/councilcommittees>

Meetings of Council streamed live and archived at Mississauga.ca/videos

1. **CALL TO ORDER**

2. **INDIGENOUS LAND STATEMENT**

"Welcome to the City of Mississauga Council meeting. We would like to acknowledge that we are gathering here today on the Treaty Lands and Territory of the Mississaugas of the Credit, and the traditional territories of the Anishinaabe, Haudenosaunee, Wyndot and Huron people. We also acknowledge the many First Nations, Inuit, Metis and other global Indigenous peoples who call Mississauga home. We welcome everyone."

3. **APPROVAL OF AGENDA**

4. **DECLARATION OF CONFLICT OF INTEREST**

5. **MINUTES OF PREVIOUS COUNCIL MEETING**

5.1 Council Minutes - June 3, 2020

6. **PRESENTATIONS- Nil**

7. **DEPUTATIONS - Nil**

8. **PUBLIC QUESTION PERIOD (15 Minutes)**

You may pre-register to present your question to Council on a matter on the agenda via WebEx during the Public Question Period, at megan.piercey@mississauga.ca by Monday, June 15, 2020 before 4:00 PM

9. **CONSENT AGENDA**

10. **MATTERS PERTAINING TO COVID-19**

10.1 Repeal of the fireworks by-law 0108-2020 to lift the prohibition related to the sale and use of fireworks during the COVID-19 Emergency Period

11. **INTRODUCTION AND CONSIDERATION OF CORPORATE REPORTS**

11.1 Clarkson Transit Station Area Study Update Report

11.2 Kipling Bus Terminal – Bus Access, Operations and Maintenance Agreement

12. **PRESENTATION OF COMMITTEE REPORTS - Nil**

13. **UNFINISHED BUSINESS**

14. **PETITIONS - Nil**

15. **CORRESPONDENCE - Nil**

16. **NOTICE OF MOTION - Nil**

17. MOTIONS

- 17.1 To close to the public a portion of the Council meeting to be held on June 17, 2020 to deal with various matters. (See Item 22 Closed Session)

18. INTRODUCTION AND CONSIDERATION OF BY-LAWS

- 18.1 A by-law to appoint a Chief Building Official, Deputy Chief Building Official and Inspectors for the enforcement of the Building Code Act, 1992, as amended, for the City of Mississauga and to repeal By-law 0076-2019

- 18.2 A by-law to authorize entering into the Kipling Bus Terminal Bus Access, Operations and Maintenance Agreement with Metrolinx

Item 11.2

- 18.3 A by-law to amend Traffic By-law 555-2000 regarding U-Turn prohibition on Bloor Street at Bridgewood Drive

GC-0133-2020 / March 25, 2020

- 18.4 A by-law to amend Traffic By-law 555-2000 regarding amending parking on Lakeside Avenue

GC-0133-2020 / March 25, 2020

- 18.5 A by-law to transfer funds from the Cash in Lieu of Parkland Reserve Fund (Account A32121) to Land Acquisition Parkland (F-585) (PN 20-304), and Land Acquisition – Parkland (F-586) (PN 20-305)

Resolution 0171-2020 / June 3, 2020 / Resolution 0172-2020 / June 3, 2020

19. MATTERS PERTAINING TO REGION OF PEEL COUNCIL

20. COUNCILLORS' ENQUIRIES

21. OTHER BUSINESS/ANNOUNCEMENTS

22. CLOSED SESSION

(Pursuant to Subsection (2) of the Municipal Act, 2001)

- 22.1 A proposed or pending acquisition or disposition of land by the municipality or local board: QEW Credit River Active Transportation Crossings (Wards 1, 2, 7 and 8)

23. CONFIRMATORY BILL

A by-law to confirm the proceedings of the Council of The Corporation of the City of Mississauga at its meeting held on June 17, 2020.

24. ADJOURNMENT

City of Mississauga

Corporate Report



<p>Date: June 10, 2020</p> <p>To: Mayor and Members of Council</p> <p>From: Shari Lichterman, CPA, Commissioner of Community Services</p>	<p>Originator's files:</p> <hr/> <p>Meeting date: June 17, 2020</p>
---	---

Subject

Repeal of the fireworks by-law 0108-2020 to lift the prohibition related to the sale and use of fireworks during the COVID-19 Emergency Period.

Recommendation

That By-law 0108-2020 be repealed to lift the prohibition related to the sale and use of fireworks during the COVID-19 emergency period in accordance with the Corporate Report dated June 10, 2020 from the Commissioner of Community Services and that the said amendments be effective on the date of Council's approval.

Background

On April 24, 2020 Council approved amendments to Fireworks related by-laws to prohibit the sale and use of fireworks for the period of the emergency related to COVID-19 declared by the Province of Ontario or to a date beyond the emergency period as determined by the Commissioner of Transportation and Works.

The prohibition was put in place in an effort to ensure gatherings would not exceed provincial guidelines and make physical distancing challenging. There was also concern for the staffing resources to both Compliance & Licensing and Fire and Emergency Services related to complaints received from the public.

At the June 10, 2020 Council meeting staff were directed to bring a report back to Council to lift the prohibition.

Comments

Given the changes to the Provincial restrictions related to group gatherings and after reviewing the experience of other Greater Toronto Area (GTA) communities that permitted fireworks over the Victoria Day weekend, consideration should be given to lifting the ban on the sale, use and licensing of fireworks.

Council	2020/06/10	2
---------	------------	---

By lifting the ban, the use, sale and licensing of fireworks would be allowed as described in the following by-laws:

1. 293-01 Fireworks Residents By-law – This regulates the use of fireworks by the public including restrictions on dates, times and permit requirements.
2. 340-01 Fireworks Vendors By-law – This regulates licensing for the ownership and operation of portable firework display units within the City.
3. 01-06 (Schedule 14) Business Licensing By-law – This regulates the licensing and sale of Fireworks from inside a building (not portable).

In addition to the provisions in the above by-laws, the use should also respect public health guidelines and provincial orders around physical distancing and group gatherings.

Financial Impact

There are no financial impacts resulting from the recommendation in this report.

Conclusion

As the Province continues to ease restrictions related to large gatherings it is now feasible to lift the fireworks restrictions related to the sale, use and licensing of fireworks on all permitted holidays with due consideration given to public health guidelines.



Shari Lichterman, CPA, Commissioner of Community Services

Prepared by: Tim Beckett, Fire Chief/Director of Emergency Management

City of Mississauga

Corporate Report



Date: June 5, 2020

To: Mayor and Members of Council

From: Andrew Whittemore, M.U.R.P., Commissioner of
Planning & Building

Originator's files:
CD.21-CLA

Meeting date:
June 17, 2020

Subject

Clarkson Transit Station Area Study Update Report

Recommendations

That the report titled "Clarkson Transit Station Area Study Update Report", dated June 5, 2020 from the Commissioner of Planning and Building be received and that staff be directed to proceed with next steps as outlined in this report.

Report Highlights

- The Province's "A Place to Grow 2019" requires municipalities to plan for intensification around transit corridors by delineating Major Transit Station Areas (MTSAs) to meet minimum densities. Mississauga has approximately 64 existing and planned MTSAs.
- The Clarkson Transit Station Area Study (TSA) has been initiated as a pilot study to provide a planning framework that will guide future transit orientated development in the area to achieve the minimum density as prescribed by the Growth Plan.
- The additional growth required to meet the minimum density could be achieved with the introduction of mixed use development, including residential uses, or continuing with only employment uses within the Southdown Employment Area.
- A comprehensive Air Quality Study is required before staff will contemplate any residential/sensitive use requests from landowners within the Southdown Employment Area.

Background

A Major Transit Station Area (MTSA) is defined as an area within an approximate 500 to 800 metre radius of an existing or planned transit station or a stop, representing about a 10-minute walk. The provincial Growth Plan for the Greater Golden Horseshoe 2019 (update from 2017)

requires municipalities to plan for MTSA's to achieve minimum density targets of 150 residents and jobs combined per hectare (ha) at GO rail stations and 160 residents and jobs combined per ha at Light Rail Transit/Bus Rapid Transit stations.

Mississauga has a total of approximately 64 existing and planned MTSA's. The Region of Peel (Region) in coordination with the City of Mississauga (City) is required by the Province to lead the delineation of MTSA boundaries. The Region has initiated the regional MTSA study with their first community meeting held in July 2019. The Region is currently working on drafting MTSA policies, which are to be presented to Regional Council in June 2020. Community engagement is scheduled to occur this fall and a recommendation report is expected to be presented to Regional Council by early 2021.

Following a Regional Official Plan amendment to incorporate the MTSA boundaries, the City will amend its Official Plan to do the same, in addition to identifying appropriate land uses, building heights and other policies to meet the minimum density targets. Alternative density targets may also be approved by the Minister of Municipal Affairs and Housing.

Considering the Province's plan for Regional Express Rail¹ on the Lakeshore West GO rail corridor, the Growth Plan identifying this line as a Priority Transit Corridor² and the potential opportunities for intensification on lands surrounding the Clarkson GO station, staff initiated the [Clarkson Transit Station Area Study](#) as a pilot MTSA study in coordination with the Region.

Comments

The Clarkson Transit Station Area Study (TSA) is a comprehensive planning exercise to evaluate the potential intensification opportunities and constraints towards creating a vibrant, walkable and transit supportive community in the area surrounding the Clarkson GO Station. The following general objectives framed the basis of the Study:

- Review the existing and planned functions of the Clarkson- Lorne Park neighbourhood, Clarkson Village and Southdown Employment Area for lands in proximity to the Clarkson GO Station.
- Delineate the Clarkson GO MTSA boundary and evaluate the potential of the area to accommodate the minimum density of 150 residents and jobs combined per ha, as mandated by the Growth Plan 2019.
- Engage the local community and businesses, landowners and other stakeholders throughout the process to identify existing opportunities, address challenges and obtain input for future development within the area towards creating a transit supportive community.
- Evaluate the impacts of intensification with a mix of uses, such as residential, while considering its proximity to existing industries.

¹ Through Regional Express Rail (RER) program, Metrolinx has planned electrification of the Lakeshore West GO corridor to provide 15 minute two-way all day service.

² Priority Transit Corridors are identified in the Growth Plan 2019 (Schedule 5). Priority Transit Corridors include planned or under implementation higher order transit corridors, i.e. transit corridors that have their own dedicated right-of-way such as GO rail lines, light rail transit, bus rapid transit, and subways and, are targeted for intensification to support transit viability. Accordingly, the Kitchener GO rail corridor, Lakeshore GO west rail corridor, 403 Transitway and Hurontario LRT are identified as Priority Transit Corridors within Mississauga as per the Growth Plan.

- Assess the current retail market environment surrounding the GO station and within the Clarkson Village and identify any future impacts with increased growth around the GO station.
- Develop a preferred plan, policy directions and implementation framework for the MTSA boundary area.


This report provides an update on four key study components:

- MTSA Boundary Area
- Target Density Analysis
- Land use Compatibility Analysis
- Clarkson GO MTSA - Air Quality Study Requirements

MTSA Boundary Area

As required by the Growth Plan, a draft boundary of Clarkson GO MTSA has been delineated considering several factors including an approximate 10 minute walking distance within 500 to 800m radius of the Clarkson GO station, land use designations, parcel fabric and potential for intensification, as shown in Figure 1 below.

Figure 1: Draft boundary of Clarkson GO MTSA



Council	2020/06/05	4
---------	------------	---

The boundary area surrounding the Clarkson GO Station includes a diverse range of land use designations within three Character Areas, namely, Clarkson-Lorne Park Neighbourhood Area, Clarkson Village Community Node and Southdown Employment Area.

- Clarkson-Lorne Park Neighbourhood is located to the north of the Clarkson GO Station and south-east of the Southdown Road. This is a stable residential neighbourhood comprised of single detached houses, townhouses and mid-rise residential buildings up to 8 storeys.
- Clarkson Village Community Node lies to the east of the Clarkson GO Station and Southdown Road, which comprises of a mix of street related shops with apartments above and some plazas along the “main street” of Lakeshore Road. Residential uses primarily consist of townhouses and buildings ranging in height from 8 to 22 storeys, the tallest buildings being closest to the Clarkson GO Transit Station.
- Southdown Employment Area is located to the south of the Clarkson GO Station and west of the Southdown road, which primarily includes heavy to light industrial establishments. Part of the Southdown Employment area, immediately south of the Clarkson GO Station is designated as mixed use, which majorly comprises of commercial and retail uses surrounded by large parking areas, including the Clarkson Crossing Shopping Centre. The mixed use designated lands within Southdown Employment Area only permit employment, retail and commercial related uses on such sites and prohibit non-employment uses such as residential.
- Other uses within the area include a City owned works yard, parks and open spaces and the Canadian Tire heritage designated gas station just north of the GO station.

The boundary area with existing conditions analysis was presented to the community and stakeholders to seek their input and frame the vision and guiding principles for the Clarkson TSA Study. Members of the public were particularly interested in improving the vibrancy of the area, increasing multi-modal connections to the GO station and creating more park spaces.

Landowners within the boundary were generally supportive of allowing more intensification in the area and many requested mixed-use (including residential) permissions where they presently do not exist. Some landowners just outside the boundary expressed a desire for the MTSA boundary to be expanded to capture more lands (particularly to the west).

During the community meetings, concerns were raised about the proximity of the western boundary to existing industries within Southdown Employment Area and how the findings of the Clarkson Airshed Study, 2010 were going to be addressed (see below).

Target Density Analysis

The minimum density of 150 residents and jobs per ha can be accommodated by planning for both jobs (offices) and/ or residential uses within the boundary area. To meet this minimum target density, an addition of approximately 6,000 residents and/ or jobs is required within the boundary area.

To test the potential of the boundary area to accommodate the minimum density target of 150 residents and jobs per ha, three redevelopment concepts were prepared. Each option illustrated

how the additional required growth could be achieved by varying the heights and types of buildings on potential redevelopment sites.


- Option 1 'Uniform or Balanced approach' - Density distribution visualized mid-rise buildings ranging from three to ten storeys, proposed on all potential development sites in the boundary area.
- Option 2 'Transitional approach' – Density distribution visualized tallest buildings ranging from 12 to 16 storeys on potential sites closest to the GO station, with heights transitioning down to mid-rise and low-rise buildings ranging from three to eight storeys to relate with the height and character of the surrounding area and existing neighbourhoods towards the edge of the boundary area.
- Option 3 'Central approach' – Density distribution visualized majority of the redevelopment as high-rise buildings ranging from 26 to 40 storeys on a limited number of redevelopment sites located adjacent the GO station.

These options were presented at a community workshop and on an online survey. The majority of the community members were in favour of Option 2 – Transitional approach as the most preferred scenario.

Land-use Compatibility Analysis

A majority of the potential redevelopment sites in the Clarkson GO MTSA boundary are located south of the Clarkson GO station and within the Southdown Employment Area, as shown in Figure 2 below.

Figure 2: Potential Redevelopment Sites within Clarkson GO MTSA boundary



An environmental analysis was conducted to review the types of local industries in the Southdown Employment Area to determine land use compatibility requirements, including a review of the Clarkson Airshed Study, 2010 findings. The environmental report made several recommendations to address the potential introduction of non-employment uses such as residential uses within the Clarkson TSA and the Southdown Employment Area. (Refer report in Appendix 1)

The Southdown Employment Area accommodates some of the largest manufacturing and long-standing industries in the City. These industries require large sites, lake and/or rail access and most importantly substantial buffering from sensitive uses³ as per the current provincial D-6 guidelines to ensure land use compatibility. Environmental analysis conducted for Clarkson TSA study indicates that the areas proposed for redevelopment fall within the area of influence of these industries (Refer to Appendix B of the report in Appendix 1).

Land use policies for Southdown Employment Area do not permit development of residential uses and the Province has identified Southdown Employment Area as a part of a Provincially Significant Employment Zone (2019). As such, a land use conversion process is required to be conducted by the Region and approved by the Province, before amendments to the City's Official Plan permitting residential uses can be considered.

Considering current land use permissions, intensification on such sites can presently only occur in the form of employment (i.e. planning for addition of jobs). However, market demand for high-density employment uses (offices) is presently not strong in the area.

Introducing residential use permissions to lands on the eastern edge of the Southdown Employment area would greatly accelerate the creation of a transit oriented community. It would also not result in the displacement of any major industries on the lands since they are currently occupied by retail users. However, further analysis is required to ensure that such sensitive uses are not adversely impacted by and are compatible with the operations of the existing industries and employment uses outside the MTSA boundary.

Clarkson Airshed Study

The Province had commissioned the Clarkson Airshed Study in 2010, which identified concerns with local air quality. The study identified local industries, truck traffic and the QEW corridor as significant local sources of pollutants taxing the Clarkson airshed.

Following the findings of the Clarkson Airshed Study, recent monitoring data indicate that there has been a general improvement in air quality within the area. Although such data is not conclusive, as it does not capture emissions of all major pollutants including Volatile Organic Compounds (VoCs), as identified in the Clarkson Airshed Study. As such, the environmental analysis conducted for the Clarkson TSA study recommends that an air quality study be undertaken prior to considering any sensitive uses on the identified parcels within the study area. (Refer to Figure 6 and 7 of the report in Appendix 1).

Clarkson GO MTSA - Air Quality Study Requirement

Staff are recommending an air quality study be prepared before residential uses are contemplated along the eastern edge of the Southdown Employment Area. The air quality study

³ Sensitive land uses are non-employment uses including and not limited to schools, daycares, places of worship, healthcare facilities and residential land uses.

Council	2020/06/05	7
---------	------------	---

would account for results generated through two processes involving an Ambient Air Quality Monitoring program and Dispersion Modelling. Findings of the air quality monitoring will provide a comprehensive representation of the ambient air quality of the Clarkson TSA. While, dispersion modelling will estimate cumulative impacts of all industries within the area to help analyze the local air quality concentrations and meteorological conditions such as wind direction and terrain levels impacting proposed heights and land uses at block levels within Clarkson TSA.

The Air Quality Monitoring program is required to be conducted for a minimum of six months, including the summer period. The current COVID-19 situation has resulted in reduced economic activity, with many businesses being inactive or operating at reduced capacity and truck and vehicular traffic volumes being relatively lower. As such, air quality monitoring conducted in the next coming months may not accurately represent typical ambient air quality concentrations. Accordingly, it is recommended that approval be received from the City and their Consultants prior to proceeding with any air quality monitoring program at this time.

A Terms of Reference (ToR) outlining the requirements to conduct the air quality study has been drafted (Appendix 2).

The air quality study will assist staff to:

- Determine the status of current air quality of the area.
- Determine whether it is appropriate and safe to introduce sensitive land uses within the eastern boundary of the Southdown Employment Area and Clarkson GO MTSA.
- Recommend any required mitigation measures as needed.

Next Steps:

Terms of Reference to be shared with Landowners

Staff have been in discussions with Slate Asset Management LP, the landowner of 2105- 2075 and 2077-2087 Royal Windsor Dr. who would like to determine whether the City would consider a mixed use development including residential land-uses on their site. Their proposed concept plan is not permitted without City, Regional and Provincial approval. Slate Asset Management LP is willing to conduct the Air Quality Study at their expense or in collaboration with other landowners of adjacent properties including Metrolinx and RioCan, who are also interested in proposing residential uses on their sites.

Staff will share the Terms of Reference with the interested landowners and other stakeholders as necessary. Given limited project resources and staff with expertise in air quality analysis, staff recommend retaining a peer reviewer to conduct a review of any Air Quality Study.

Official Plan Amendment

Staff recommend that the requirement of an Air Quality Study be included in the Official Plan, and that such study would be subject to Council approval, prior to an application for any proposed sensitive land use changes within the Clarkson MTSA or Southdown Employment Area is deemed complete. In addition, development proponents will also have to demonstrate adherence to the Province's D-Series guidelines.

Concept Plan Development

Concurrent to the land-use compatibility work, the project team continued with drafting a preferred concept plan considering elements such as a conceptual built-form, connections and public spaces, mobility and placemaking. This work will provide an implementation framework for the Clarkson TSA, subject to the recommendations of the land use compatibility study.

Financial Impact

There are no immediate financial impacts resulting from the recommendations in this report.

The cost of retaining a peer reviewer is estimated to be between \$10,000 to \$30,000, which would be incurred after an air quality study is submitted by an applicant to the City and is proposed to be funded through the City Planning Strategies capital project 17975 account #715601 for MTSA work.


Conclusion

Clarkson TSA Study will lay an implementation framework to guide future growth within the area to achieve the minimum density target of 150 residents and jobs per hectare. The additional growth could be achieved with the introduction of mixed use development including residential uses, or continuing with only employment types of uses as permitted within the Southdown Employment Area. To determine whether it is appropriate to consider residential use permissions on lands within the Southdown Employment Area, staff are recommending an Air Quality Study be completed. A comprehensive Air Quality Study will ensure any potential new development is appropriate and safe for future residents, while respecting the economic viability of the Southdown Employment Area.

Attachments

Appendix 1: Clarkson Air Quality, Noise & Vibration and Radiofrequency Compatibility Overview Study

Appendix 2: Terms of Reference - Air Quality Study



Andrew Whitemore, M.U.R.P., Commissioner of Planning and Building

Prepared by: Romas Juknevičius, City Planning Strategies
Taral Shukla, City Planning Strategies



THE PLANNING PARTNERSHIP

Clarkson Air Quality, Noise & Vibration and Radiofrequency Compatibility Overview Study

Table of Contents

1.0	Introduction	1
2.0	Description of the Study Area	1
2.1	Study Area	1
2.2	Preliminary Preferred MTSA Plan	2
2.3	Local Industries	3
3.0	Applicable Acts, Regulations, and Guidelines	4
3.1	Environmental Protection Act.....	4
3.2	D-Series Guidelines	6
3.2.1	Ontario's Ambient Air Quality Criteria (AAQC)	8
3.3	Ontario Regulation 419/05 – Air Quality	9
3.4	NPC-300	10
3.5	NPC-207	11
3.6	Health Canada Radiofrequency Safety Code 6 (2015)	11
4.0	Air Quality Review	13
4.1	Existing Local Air Quality	13
4.1.1	Clarkson Airshed Study	13
4.1.2	Local Air Quality – Current	16
4.2	Local Meteorology	17
4.3	Existing Industries – Air Quality	18
4.4	MTSA Plan and Study Considerations	22
4.4.1	Nuisance Contaminants (Dust and Odour)	23
4.4.2	General Air Contaminants.....	25
4.5	Recommendations	25
5.0	Noise and Vibration Review	28
5.1	Noise Impact	28
5.2	Vibration Impact	29
5.3	Existing Industries – Noise & Vibration Review	31
5.4	Implications of Noise and Vibration on the Proposed Development Plan	33
5.5	Recommendations	35

6.0	Radio Frequency Review	37
6.1	Analysis and Impacts.....	37
6.2	Mitigation and Recommendation	37
7.0	Closure	38
8.0	References	39

Figures

Figure 1: Clarkson MTSA Southdown Employment Area and the Clarkson Transit Station Area Boundary	2
Figure 2: MTSA as of August 26 th , 2019	3
Figure 3: Wind Rose for 2003 through 2005 from Toronto Island Airport	18
Figure 4: MTSA (shown in pink) and Industries Considered For this Study	22
Figure 5: MTSA Plan with Building Heights Represented in each Block	23
Figure 6: Development Blocks where Nuisance Impact Studies are Recommended (shown in purple).....	24
Figure 7: Development Blocks where General Air Contaminants should be assessed (shown in purple).....	25
Figure 8: Typical Sources of Noise and Threshold Interference	29
Figure 9: Typical Vibration Sources, Levels and Human /Structural Response	31

Tables

Table 1: Selected Provincial Environmental Regulations and Guidelines.....	5
Table 2: MECP Guidelines on Compatibility Between Industry and Sensitive Uses	8
Table 3: Stationary Noise Exclusionary Limits	11
Table 4 – Electric Field Strength Reference Levels – Health Canada	12
Table 5 – Magnetic Field Strength Reference Levels – Health Canada	12
Table 6: Clarkson Airshed Study 24-hr NO ₂ Monitoring Results	14
Table 7: Clarkson Airshed Study 1-hr NO ₂ Monitoring Results	14
Table 8: Clarkson Airshed Study PM _{2.5} Monitoring Results	15
Table 9: – Clarkson Airshed Study PM ₁₀ Monitoring	15
Table 10: Clarkson Airshed Study Selected VOC Monitoring Results	16
Table 11: MECP NO _x Ambient Air Quality Monitoring Data (2005-2006, and 2016-2017)	16

Table 12: MECP PM _{2.5} Ambient Air Quality Monitoring Data (2005-2006, and 2016-2017).....	17
Table 13: Local Industries within the MTSA – Air Quality.....	19
Table 14: Commonly applied control technologies for air quality and Odour.....	26
Table 15: Local Industries within the MTSA	32
Table 16: Commonly applied control technologies for noise and vibration.....	35

Appendices

- A Radio Frequency Analysis
- B Guideline D-6 Industrial Classification

1.0

Introduction

The City of Mississauga (the City) is undergoing a planning program to intensify land uses surrounding the Clarkson Major Transit Station Area (MTSA) that would also change the intensity of uses in the area. As part of this program, the City is proposing to develop policies for land development that can achieve a minimum density of 150 residents and jobs per hectare. This translates to a minimum addition of 4,000 to 5,000 residents and jobs within 500 to 800 m of the Clarkson GO Station. To achieve this target requires that parts of the lands within the Southdown Employment Area (SEA) be occupied by offices or mid to high density residential uses.

The SEA is considered one of the City's heaviest industrial areas with significant economic importance, and includes a range of industrial uses (e.g., machinery fabrication, automotive part manufacturing, chemical manufacturing, aggregate facilities, wastewater treatment plants, etc.) as well as a blend of mixed-use lands, commercial lands, and undeveloped lands. Based on the City's 2015 Municipal Comprehensive Review of Employment Lands, in comparison to other employment areas within the City's boundary the SEA has one of the third largest shares of vacant land, totalling approximately 154 hectares (380 acres). The existing residential land uses in the immediate vicinity of the employment area are a mix of medium- and low-density.

Introducing sensitive land uses in close proximity to industry can result in adverse effects at the sensitive land uses. The MTSA proposal assessed in this report includes introducing a mix of commercial and residential uses in the lands within the SEA. The objective of this study is to complete a screening-level study of the MTSA proposed plan as it relates to air quality, noise, and vibration as well as radio frequency impact, in order to comment on potentially incompatible land uses and provide the City with recommendations to be able to further assess possible land-use conversions under the MTSA.

2.0

Description of the Study Area

2.1

Study Area

Approximately half of the study area is within the SEA, in the City of Mississauga (**Figure 1: Clarkson MTSA Southdown Employment Area and the Clarkson Transit Station Area Boundary**). The SEA is bound by Lake Ontario to the east, Winston Churchill Boulevard to the south, Canadian National (CN) Railway tracks to the west, and Southdown Road and 4th Road East to the north. This area is primarily zoned as 'Employment'. The north and east sides of the Employment Area are surrounded by low-rise residential neighbourhoods. On the south side, the area borders Lake Ontario. The areas immediately adjacent to the north of the SEA are CN railway tracks. The area to the north of the railway tracks consist of mixed

commercial and residential uses. The Clarkson Go Station is located at the north-east corner of the SEA, in proximity to the Southdown Road and Royal Windsor Drive intersection.




Figure 1: Clarkson MTSA Southdown Employment Area and the Clarkson Transit Station Area Boundary

(Source: Clarkson TSA Study, July 23 2019)

2.2 Preliminary Preferred MTSA Plan

The proposed Preliminary Preferred MTSA Plan (The Plan) being assessed is centered on the Clarkson Mississauga GO Transit station, and generally includes the greater area adjacent to the Royal Windsor Drive, Lakeshore Road West and Southdown Road intersection (approximately 80 hectares). The Plan proposes to intensify the usage of the surrounding Clarkson MTSA and also proposes changes to some of its use. This is proposed to include having some green lands, mixed use, office, open space, residential

(medium and high density), and heritage sites. The Plan also includes enhanced streetscapes, bike lanes, multi-use trails, retail at-grade, and new parks. Proposed mixed use, residential and office space areas are primarily proposed to be to the West of Southdown Road with development heights generally ranging from 5 to 25 storeys.

Roughly half of the Plan area is located within the Southdown employment Area, which includes Class I, II, and II industrial facilities. Some areas near and within the Plan include industrial commercial, industrial general, industrial heavy, and utility usages. Existing residential areas are primarily located to both the east of the Southdown Road and to the North-West of the Clarkson GO station and rail line. Existing employment and commercial areas are generally located along the Southdown Road and Royal Windsor Drive. The MTSA is presented in **Figure 2: MTSA as of August 26th, 2019**.




Figure 2: MTSA as of August 26th, 2019

2.3 Local Industries

Within the SEA there are over 50 industries, including manufacturers in the automotive, chemical manufacturing and transport, cement, transportation and logistics, aggregate, and wastewater treatment sectors. Also included in area is the CFRB1010 AM transmission antenna array, which broadcasts Radio Frequency (RF) at 1,010 kHz. This assessment is focussed on compatibility between

these industries and the proposed sensitive land uses within the MTSA. An in-depth consideration of the industries in the vicinity of the MTSA is presented later in the report.

3.0 Applicable Acts, Regulations, and Guidelines

This section provides an overview of the provincial framework and processes that establish the basis for this high-level environmental impact review in the context of land use planning.

3.1 Environmental Protection Act

The 1990 *Ontario Environmental Protection Act* (EPA) is the overarching environmental law in the Province. The purpose of the Act [Section 3. (1)] is “to provide for the protection and conservation of the natural environment”. In general, the management of impacts to individual environmental media (e.g., air, water, soil) is addressed within separate regulations enacted under the EPA. From a land-use compatibility context, Section 9 and Section 14.1 of the EPA are applicable to the understanding of an industry’s obligations. Section 9 (1) states:

- “No person shall, except under and in accordance with an environmental compliance approval,*
- (a) use, operate, construct, alter, extend or replace any plant, structure, equipment, apparatus, mechanism or thing that may discharge or from which may be discharged a contaminant into any part of the natural environment other than water; or*
 - (b) alter a process or rate of production with the result that a contaminant may be discharged into any part of the natural environment other than water or the rate or manner of discharge of a contaminant into any part of the natural environment other than water may be altered...”*

Under Section 9 of the EPA it is clearly stated that all industrial uses require an Environmental Compliance Approval (ECA) to operate. This is discussed further under Ontario Regulation 419/05 (the regulation which describes the supporting assessments and documents to obtain an ECA). In summary, Section 9 requires that all industries undergo a technical assessment, including modelling, of their air and noise emissions and the impacts on the surrounding environment. Section 14 of the EPA states:

“...a person shall not discharge a contaminant or cause or permit the discharge of a contaminant into the natural environment, if the discharge causes or may cause an adverse effect...”

The implication of these sections is that all industries which have discharges to the environment – including air emissions and noise emissions – must operate under an approval and, regardless of their approval, may not cause an adverse effect. The EPA defines an adverse effect as:

- “(a) impairment of the quality of the natural environment for any use that can be made of it,*
- (b) injury or damage to property or to plant or animal life,*
- (c) harm or material discomfort to any person,*
- (d) an adverse effect on the health of any person,*
- (e) impairment of the safety of any person,*
- (f) rendering any property or plant or animal life unfit for human use,*

*(g) loss of enjoyment of normal use of property, and
(h) interference with the normal conduct of business;”*

The adverse effect clause in the EPA is often used in the assessment of nuisance complaints such as noise or odour in a land use compatibility context. This is due to the fact that nuisance contaminants are not assessed at all locations off-site in the preparation of an Environmental Compliance Approval (ECA). For example, odours are not typically assessed at an industrial facility. Therefore, when considering land use changes which may introduce new sensitive receptors in an area, it is important to consider both an industry’s current ECA and their operations with respect to nuisance contaminants.

The Ministry of the Environment, Conservation and Parks’ (MECP) regulations and guidelines for air, noise and vibration fall under the EPA. **Table 1** provides an overview of the provincial regulations and guidelines that are applicable to the regulation and assessment of air, noise, and vibration.

Table 1: Selected Provincial Environmental Regulations and Guidelines

	Regulations and Guidelines	Environmental Studies and Requirements
General	<ul style="list-style-type: none"> • D-Series Land Use Compatibility Guidelines • D-1 Guideline: Land Use Compatibility • D-2 Compatibility between Sewage Treatment and Sensitive Land Use • D-3 Environmental Considerations for Gas or Oil Pipelines and Facilities • D-4 Land Use On or Near Landfills and Dumps • D-6 Guidelines: Compatibility between Industrial Facilities 	<ul style="list-style-type: none"> • Land use compatibility studies and mitigation measures
Air Quality	<ul style="list-style-type: none"> • Ontario Regulation 419/05 (Air Pollution – Local Air Quality) • Ontario Regulation 1/17 (Registrations under Part II.2 of the Act – Activities Requiring Assessment of Air Emissions) • Air Contaminants Benchmarks List: Standards, Guidelines and Screening Levels for Assessing Point of Impingement Concentrations of Air Contaminants • Ontario’s Ambient Air Quality Criteria - Sorted by Contaminant Name 	<ul style="list-style-type: none"> • Environmental Compliance Approval (ECA) • Environmental Activity and Sector Registry (EASR) • Emission Summary and Dispersion Modelling (ESDM) Report • Fugitive Dust Management Plan
Noise/Vibration	<ul style="list-style-type: none"> • NPC-300 Environmental Noise Guideline: Stationary and Transportation Sources • NPC-207 – Impulsive Vibration in Residential Buildings 	<ul style="list-style-type: none"> • Air & Noise Environmental Compliance Approval • Environmental Activity and Sector Registry (EASR) • Acoustic Assessment Report • Noise Abatement Action Plan

	Regulations and Guidelines	Environmental Studies and Requirements
Odour	<ul style="list-style-type: none"> Ontario Regulation 419/05 (Air Pollution – Local Air Quality) Ontario Regulation 1/17 (Registrations under Part II.2 of the Act – Activities Requiring Assessment of Air Emissions) 	<ul style="list-style-type: none"> Air & Noise Environmental Compliance Approval Environmental Activity and Sector Registry (EASR) Odour Best Management Practices Plan Odour Control Report

3.2 D-Series Guidelines

The MECP has published *Land Use Compatibility Guidelines*, referred to as the D-Series of Guidelines (1995). The D-Series Guidelines were prepared under the legislative authority of the *Planning Act*, the EPA, and the Environmental Assessment Act (EAA). The intent of the Guidelines is to minimize or prevent, through the use of buffers and separation of uses, the encroachment of incompatible land uses. The guideline delegates responsibility to the planning authorities within the Province to identify when the D-Series of Guidelines is applicable and requires they be followed where needed. It is important to note that this extends both to the introduction of sensitive land uses on existing industrial lands and vice versa. While the Guidelines were designed to deal with new applications, they provide a useful benchmark for understanding land use conflicts / incompatibility. The Guideline provides definition of three classes of industry (Class I, Class II, and Class III), as well as minimum recommended separation distances and potential areas of influence for each class.

The industrial facilities classes are defined in the Land Use Compatibility guidance document as followed:

Class I Industrial Facility

“A place of business for a small scale, self-contained plant or building which produces/stores a product which is contained in a package and has low probability of fugitive emissions. Outputs are infrequent, and could be point source or fugitive emissions for any of the following: noise, odour, dust and/or vibration. There are daytime operations only, with infrequent movement of products and/or heavy trucks and no outside storage.”

Class II Industrial Facility

“A place of business for medium scale processing and manufacturing with outdoor storage of wastes or materials (i.e., it has an open process) and/or there are periodic outputs of minor annoyance. There are occasional outputs of either point source or fugitive emissions for any of the following: noise, odour, dust and/or vibration, and low probability of fugitive emissions. Shift operations are permitted and there is frequent movement of products and/or heavy trucks during daytime hours”

Class III Industrial Facility

“A place of business for large scale manufacturing or processing, characterized by: large physical size, outside storage of raw and finished products, large production volumes and continuous movement of products and employees during daily shift operations. It has frequent outputs of major annoyance and there is high probability of fugitive emissions.”

The D-Series Guidelines do not provide for a pass/fail assessment of compatibility between industrial and sensitive land uses, but recommend when a technical assessment should be performed. Based on the classes described above, the Ministry has recommended Potential Influence Areas for industries. These areas represent the separation distance between industry and sensitive receptors within which studies should be performed to demonstrate the uses are compatible.

The Land Use Compatibility: Procedure for Implementation Guideline (D-1-1 Land Use Compatibility and Procedure for Implementation) provides guidance for how land use authorities can protect people and the environment from nuisance impacts from industrial areas. The D-1-1 Guideline explicitly notes that developers of land hold the primary responsibility for identifying and implementing the necessary measures to make a development environmentally acceptable. The MECP further states that this Guideline must be considered during the development applications, land use related plans, as well as municipal official plans, amendments and municipal secondary plans. Section 7.6 of Guideline D-1-1 provides guidance on when site plan control can be used as a tool for requiring study under the D-Series. To this extent a municipality may consider whether changes to the Official Plan are appropriate to allow for site plan control which allows requirements for specific mitigation on a per-development basis.

Section 7.5 of the D-1-1 Guideline indicates that plans of larger developments (specifically subdivision/condominium and consents to sever) located within an area of influence only be permitted *“...if there are no compatibility problems, or if the proponent can demonstrate how incompatibilities will be satisfactorily mitigated to the level of a trivial impact.”*

The D-6 Guidelines’ three types of industrial facilities and their respective potential areas of influence are summarized in **Table 2**. The MECP acknowledges that it may be difficult to achieve the recommended minimum separation distance in designated mixed use areas. The guidelines indicate that it is the responsibility of the proponent to carry out the appropriate land use compatibility studies. Compatibility studies are part of the development review process, and involve site-specific modelling exercises based on the ‘worst case scenario’. These studies help in determining the appropriateness of introducing sensitive land uses in proximity of industrial establishments.

Table 2: MECP Guidelines on Compatibility Between Industry and Sensitive Uses

Facility Type	Definition	Areas of Influence	Recommended Minimum Separation Distance
Class I Industrial Facility	<ul style="list-style-type: none"> • Small scale and self-contained plant or building • Stores/produces product in a contained package with low probability of fugitive emissions • Infrequent outputs which could be point source or fugitive emissions for any of the following: noise, odour, dust and/or vibration • Operates only during the daytime • Infrequent movement of products and/or heavy trucks 	70 metres	20 metres
Class II Industrial Facility	<ul style="list-style-type: none"> • Medium scale processing/manufacturing building • Outdoor storage of wastes or materials (i.e., it has an open process) • Occasional outputs of either point source or fugitive emissions for any of the following: noise, odour, dust and/or vibration, and low probability of fugitive emissions • Allows for shift operations and frequent movement of products during daytime hours 	300 metres	70 metres
Class III Industrial Facility	<ul style="list-style-type: none"> • Large scale manufacturing or processing business • Includes outside storage of raw and finished products, large production volumes, continuous movement of goods, and high probability of fugitive emissions • Frequent outputs of major annoyance and daily shift operations 	1000 metres	300 metres

Source: MECP, 1995

Assessments under the D-Series Guidelines typically follow the general procedure outlined in Ontario Regulation 419/05 as described in the following section. One area where Series Guidelines may differ from these procedures is in the use of Ontario's Ambient Air Quality Criteria in lieu of the Ministry's Air Contaminants Benchmark list. The D-6 Guidelines are referenced further in the technical assessment portion of this report.

3.2.1 Ontario's Ambient Air Quality Criteria (AAQC)

The AAQC are the most relevant set of air quality criteria with respect to land use compatibility assessments. Whereas the MECP's standards (described in Section 3.3) are to be used for assessing the impact of a single industry, the AAQC can be used to holistically evaluate ambient air quality in an area (i.e., considering **all** industries as well as transboundary and background contributors). In this way, the AAQC are useful to determine if a location is suitable for a proposed land use irrespective of the contribution of a single industrial source, but in consideration of all sources (industrial, transportation, etc.). Depending on the type of Air Quality (AQ) contaminants, the AAQC are based on nuisance or human health impact. Relevant AAQC's are presented in the Local Air Quality section.

3.3 Ontario Regulation 419/05 – Air Quality

The MECP's Environmental Compliance Approval (ECA) process provides a framework with which industries are required to assess their environmental impact. ECAs – or an alternative, simpler approval known as an Environmental Activity and Sector Registry (EASR) application, regulated under Ontario Regulation 1/17 – are issued by the MECP under Section 9 of the EPA. The MECP does allow for certain activities to be exempted from the requirement to hold an ECA, and the list of exemptions is included in O. Reg. 524/98. Activities that are exempt are typically lower risk, as previously determined by the MECP, such as: standby power systems, small wood fuel burning equipment (less than 50kW), and residential air conditioning units.

The MECP requires any industry applying for approval under an ECA or EASR to perform an assessment of air emissions as described in Ontario Regulation 419/05 (O.Reg 419) which pertains to local air quality. O.Reg. 419 outlines the requirements of a technical assessment as well as the standards to be used. The general process of an air quality technical assessment to obtain an ECA or EASR follows these steps:

1. Industries quantify emission rates for each point of release on site.
2. Emissions are assessed using an approved air dispersion model. Point of impingement concentrations of regulated air contaminants (e.g., NO_x, acrolein) are assessed through dispersion modelling at and beyond the property boundary of the facility being assessed. Receptor locations are defined in grid formation with varying resolutions, depending on setback distance from the subject industry (i.e., coarser resolution is used with increased distance from the facility). *Existing* discrete receptors, including elevated receptors (i.e., air intakes and balconies/terraces of multi-storey buildings) are also included in the pool of receptor locations. Nuisance impacts such as dust and odour are assessed at all *existing* discrete sensitive receptors (e.g., houses, schools, apartment buildings balconies).
3. The predicted ambient air concentrations of regulated air contaminants are compared against the Ministry's Air Contaminants Benchmark list (ACB) to determine compliance.

The implications of O.Reg 419 from a land use compatibility perspective are:

- All industries which operate in compliance with an approval will individually meet the air quality standards for regulated contaminants at all off-site locations, regardless of existing land use. These assessments do not account for the existing ambient concentrations of air contaminants.
- Adding new elevated receptors, such as medium to high density residential to an area may represent new regulatory obligations for industries and potentially lead to compliance issues, as these locations may not have been assessed during the regulatory approval process.
- Adding sensitive receptors in proximity to industry may result in compliance issues for those industries due to nuisance complaints (i.e., odour, dust complaints), as O.Reg 419 does not require assessment of nuisance complaints at most non-existing sensitive land uses.

3.4 NPC-300

The 2013 Environmental Noise Guideline: Stationary and Transportation Sources (NPC-300 Guideline) is the primary guideline used in Ontario to regulate noise emissions. The MECP introduced the Environmental Noise Guideline: Stationary and Transportation Sources (NPC-300 Guideline) in 2013 to address inconsistencies of sound level limits between previous guidelines, including NPC-205, NPC-232, LU-131 and the Noise Assessment Criteria in Land Use Planning: Requirements, Procedures and Implementation.

NPC-300 is designed to address the development of noise sensitive land uses adjacent to noise emitting facilities, including industrial and commercial facilities. Section B10 of the NPC-300 Guidelines states that it is the responsibility of the proponent to ensure that sound level criteria are met and appropriate mitigation measures are in place for stationary noise sources.

According to NPC-300, an agreement for noise mitigation must demonstrate the following:

- The stationary source has the ability to comply with the applicable sound level limits at the new noise sensitive land use;
- Provide certainty that receptor based noise control measures are implemented and maintained;
- Provide consistency for planning noise sensitive land use(s) in the proximity of stationary source(s);
- Address the continuous responsibilities of all the parties to the agreement; and,
- Describe the noise control measures and provide information about how these measures will result in compliance with the applicable sound level limits.

NPC-300 also outlines applicable noise criteria for sensitive land use development associated with surrounding industrial and commercial stationary noise sources. The noise criteria are defined using area classifications (not to be confused with the D-6 industrial classifications), which are based on the receptor's existing acoustical environment. NPC-300 area classifications are as follows:

- Class 1 – Urban Area
- Class 2 – Semi-Urban / Semi – Rural
- Class 3 – Rural Area
- Class 4 – Areas of Redevelopment and Infill

Different noise guideline limits apply to each area classification, as presented in **Table 3**.

Table 3: Stationary Noise Exclusionary Limits

Assessment Location	Time Period	Exclusionary Sound Level Limit - L_{eq} 1hr			
		Class 1	Class 2	Class 3	Class 4
Plane of window for living area or sleeping quarters	Daytime (07:00 - 19:00)	50 dBA	50 dBA	45 dBA	60 dBA
	Evening (19:00 - 23:00)	50 dBA	50 dBA	40 dBA	60 dBA
	Night-time (23:00 - 07:00)	45 dBA	45 dBA	40 dBA	55 dBA
Outdoor points of reception	Daytime (07:00 - 19:00)	50 dBA	50 dBA	45 dBA	55 dBA
	Evening (19:00 - 23:00)	50 dBA	45 dBA	40 dBA	55 dBA

3.5 NPC-207

The MECP (formerly Ministry of the Environment) publication NPC-207 is titled: *Impulse Vibration in Residential Buildings* (Nov. 1983) and it is intended to provide assessment method for determining vibration levels inside occupied residential building that are caused by operation of stationary sources of vibration at industrial facilities (e.g., stamping presses, forging hammers). The publication also provides vibration limits for frequent and infrequent impulses of vibration. The vibration limits are expressed in terms of peak vibration velocity in mm/s and duration of impulses.

3.6 Health Canada Radiofrequency Safety Code 6 (2015)

In June 2015, Health Canada issued Human Exposure Guideline limits for radiofrequency electromagnetic energy in the frequency range of 3 kHz to 300 GHz. The guide (also referred to as Safety Code 6), explains the associated potential impact of exposure to Radiofrequency (RF) fields on human health and specifies reference levels for electric and magnetic field strengths. The standards are developed based on acute exposure to RF fields that may result in localized heating or stimulation of excitable tissue (e.g., nerve stimulation). The biological response to RF fields is a function of quantum of energy absorption, which depends on the frequency, strength and orientation of the incident fields. On the receiver end (biological response), it also depends on the body mass and its electric properties. The Absorption of RF energy is described in term of Specific Absorption Rate (SAR) (Health Canada, 2015). The electric field and magnetic field standards are set based on SAR or Nerve Stimulation (NS) and are summarized in **Tables 4** and **5**, respectively.

Table 4 – Electric Field Strength Reference Levels – Health Canada

Frequency (MHz)	Reference Level Basis	Reference Level (ERL) (V/m, RMS)		Reference Period
		Uncontrolled Environment	Controlled Environment	
0.003 – 10	NS	83	170	Instantaneous
1.0 – 10	SAR	$87 / f^{0.5}$	$193 / f^{0.5}$	6 minutes

Note:

Uncontrolled environment condition refers to internal electric field strength starting at 1.10 MHz, instantaneous RMS

Controlled environment condition refers to internal electric field strength starting at 1.29 MHz, instantaneous RMS

Frequency 'f' is in MHz. NS: Nerve Stimulation SAR: Specific Absorption Rate

For instantaneous reference levels, at no time the specified levels shall be exceeded.

Table 5 – Magnetic Field Strength Reference Levels – Health Canada

Frequency (MHz)	Reference Level Basis	Reference Level (ERL) (V/m, RMS)		Reference Period
		Uncontrolled Environment	Controlled Environment	
0.003 – 10	NS	90	180	Instantaneous
1.0 – 10	SAR	$0.73 / f$	$1.6 / f$	6 minutes

Note:

Uncontrolled environment condition refers to internal electric field strength starting at 1.10 MHz, instantaneous RMS

Controlled environment condition refers to internal electric field strength starting at 1.29 MHz, instantaneous RMS

Frequency 'f' is in MHz. NS: Nerve Stimulation SAR: Specific Absorption Rate

For instantaneous reference levels, at no time the specified levels shall be exceeded.

4.0

Air Quality Review

The following describes the outline of the air quality study presented in this section:

1. Measured concentrations of selected air contaminants within the MTSA are presented in order to describe local air quality.
2. Local meteorological conditions are presented in the form of wind speed and direction. Wind conditions will dictate the dispersion of contaminants within an air shed and are important when considering the impacts of an individual industry on surrounding land uses.
3. Local industries are presented. Only those industries which are expected to contribute substantially to the local air shed have been discussed.
4. The MTSA is presented with a discussion of the design parameters which impact land use compatibility from an air quality perspective for both nuisance contaminants and general air contaminants.
5. Summary recommendations are provided.

4.1 Existing Local Air Quality

4.1.1 Clarkson Airshed Study

In 2001 in response to concerns from the local community the MECP began an ambient air quality monitoring program within the Clarkson Airshed, designated as the Clarkson Airshed Study (the CAS). The CAS focussed on identifying significant sources of air pollutants, ambient air quality monitoring, evaluating contributions from local major industry in comparison to transboundary sources, as well as investigating and discussing abatement options for local industries within the greater Clarkson region. This region is defined in the CAS as the area bounded by Chartell Road (becomes Eighth Line, north of Highway 403), Dundas Street, and Glengary Road, and Lake Ontario. The study was separated into four parts where Part 1 focused on limited monitoring within residential areas, Part 2 on greater and more detailed ambient air quality monitoring, Part 3 on assessing air quality dispersion modelling and source contribution from more distant sources, and Part 4 on ongoing monitoring. In Part 2 the Clarkson Airshed Study conducted the most detailed monitoring, including monitoring of seven pollutants being: total suspended particulates (TSP); inhalable particulate matter (PM₁₀); respirable particulate matter (PM_{2.5}); nitrogen oxides (NO_x); nitric oxide (NO); nitrogen dioxide (NO₂); and volatile organic compounds (VOCs). Monitoring was completed over 22 months at six air quality monitoring stations.

Station #46117 (Industrial East) and Station #46128 (Industrial Centre) are closest to the MTSA, (1,350 and 1,150 metres, respectively). During a subsequent phase of the study, three more ambient air quality stations were deployed for additional monitoring of selected VOCs, acrolein, acrylonitrile, and dichloromethane in the area surrounding the MTSA at the following locations:

- 2255 Royal Windsor Drive;

- 2509 Royal Windsor Drive; and,
- 2645 Royal Windsor Drive.

The results from this additional monitoring were included in an addendum to the Phase 2 Clarkson Airshed Study. Relevant Phase 2 results are presented below in the context of the MTSA.

The CAS provides a good review of historical local air quality, although it is important to note that there have been significant changes to the area's industries and air emission contributors. Unprocessed data was not included in the CAS report; results are included in this report in the statistical form they were originally presented (e.g., 98th percentile maximum). These results can be used to understand the trends in air quality within the Clarkson Airshed over the duration of the CAS.

4.1.1.1

Nitrogen Dioxide - NO₂

Results from the CAS show that 98th percentile 24 hr and maximum 1 hr ground-level concentrations of NO₂ were below the AAQC. This indicates that during the CAS, NO₂ concentrations within the airshed were typically within the “desirable concentration... used to assess general air quality resulting from all sources of a contaminant to air”¹. A summary of the result for the two stations closest to the proposed development area are provided in **Table 6** and **Table 7**.

Table 6: Clarkson Airshed Study 24-hr NO₂ Monitoring Results

Station Name	NO ₂ – 24 Hour		
	Average (2003 – 2005)	98th percentile (2003 – 2005)	Ambient Air Quality Criteria
Industrial East	14 ppb	40 ppb	100ppb
Industrial Centre	17 ppb	38 ppb	

Table 7: Clarkson Airshed Study 1-hr NO₂ Monitoring Results

Station Name	NO ₂ – Max 1 Hour			Ambient Air Quality Criteria
	2003	2004	2005	
Industrial East	74 ppb	134 ppb	53 ppb	200 ppb
Industrial Centre	50 ppb	75 ppb	70 ppb	

¹ Ontario's Ambient Air Quality Criteria, <https://www.ontario.ca/page/ontarios-ambient-air-quality-criteria-sorted-contaminant-name>, Accessed November 6th, 2019

4.1.1.2

Particulate Matter (fine fraction) - PM_{2.5}

Results from the CAS showed elevated concentrations of PM_{2.5}. The 24 hr 98th percentile PM_{2.5} concentrations were equal to the AAQC. It should be noted that this occurred infrequently (by definition 98th percentile concentrations are exceeded 2% of the time or 8 days per year for a 24-hour standard) and is not unique to the Clarkson Airshed; PM_{2.5} occasionally exceeds the AAQC in much of Southwestern Ontario. Average and 98th percentile concentrations from the CAS are summarized in **Table 8**.

Table 8: Clarkson Airshed Study PM_{2.5} Monitoring Results

Station Name	PM _{2.5} – 24 Hour		Ambient Air Quality Criteria ¹
	Average	98 th Percentile	
	2003-2005	2003-2005	
Industrial East	7 µg/m ³	27 µg/m ³	27 µg/m ³
Industrial Centre	11 µg/m ³	25 µg/m ³	

¹The Ambient Air Quality Criteria for PM_{2.5} is currently 30, however the Canada Wide Standard for this contaminant is proposed to decrease to 27 µg/m³ in 2020, therefore this value was used for conservativeness

4.1.1.3

Particulate Matter - PM₁₀

Results from the CAS showed that average 24-hour ground-level concentrations of PM₁₀ were below the AAQC. A summary of the results are provided below in **Table 9**.

Table 9: – Clarkson Airshed Study PM₁₀ Monitoring

Station Name	PM ₁₀ – 24 Hour	
	Average	Ambient Air Quality Criteria
	2003-2005	
Industrial East	17 µg/m ³	50 µg/m ³
Industrial Centre	19 µg/m ³	

4.1.1.4

Volatile Organic Compounds - VOCs

Sampling results from the CAS showed elevated ground-level concentrations of certain volatile organic compound (VOCs). **Table 10** shows the results of the initial CAS along with results of additional monitoring within the SEA of selected VOCs, including acrolein, which was completed in an addendum to the CAS. It can be seen that for the VOCs presented in **Table 10**, there were exceedances of the AAQC. At the time of the study there were no AAQC or ACB limits for benzene. These results suggest that the MTSA may require consideration from an air quality perspective prior to implementing any proposed changes to land use within the study area, especially for any residential developments.

Table 10: Clarkson Airshed Study Selected VOC Monitoring Results

Contaminant	Location of Max	Max (µg/m³)	Average (µg/m³)	Ambient Air Quality Criteria		
				Threshold	Limiting Effect	Averaging Time
Benzene	Industrial East	0.92 µg/m³	0.82 µg/m³	0.45 µg/m³	Health	Annual
Dichloromethane ^t	Industrial Centre	245.00 µg/m³	NA	220.0 µg/m³	Health	24 hr
Acrolein ^{i,t}	2645 Royal Windsor	3.94 µg/m³	NA	0.40 µg/m³	Health	24 hr
	2509 Royal Windsor	2.14 µg/m³	NA			
	2255 Royal Windsor	1.85 µg/m³	NA			

ⁱ Data for Acrolein summarized from the *Clarkson Airshed Study - A Scientific Approach to Improving Air Quality - Addendum to Part II - The Ambient Air Monitoring Program: South Mississauga (Clarkson) and Oakville Sampling Results for Acrolein, Acrylonitrile and Dichloromethane in Ambient Air, Summer 2007*

^t Average ground-level concentrations were not available at the time of this report.

4.1.2 Local Air Quality – Current

It is recognized that the data collected in the CAS may not be representative of the current air quality in the MTSA. A number of factors can change within an area which will act to improve air quality, including but not limited to: industrial relocation, improvement in industrial processes, improvements in on-road vehicle performance, and the adoption of zero-emission technologies. Considering this, recent local air quality data was reviewed from the Ministry of the Environment Conservation and Parks (MECP) air pollutant monitoring network to identify if there are any trends in the data in the decade since the CAS was completed. The MECP air pollutant monitoring station nearest to the proposed development area is located at 3359 Mississauga Road N., in Mississauga. NO_x (1 hr average and 24 hr average) and PM_{2.5} (24 hr average) data were obtained from this station for the periods of 2005-2006 and 2016-2017 and are summarized respectively below in **Table 11** and **Table 12**.

Table 11: MECP NO_x Ambient Air Quality Monitoring Data (2005-2006, and 2016-2017)

Contaminant		2005-06 (1 hour)	2016-17 (1 hour)	2005-06 (24 hour)	2016-17 (24 hour)
NO _x	Max	261.0 ppb	149.0 ppb	107.6 ppb	64.9 ppb
	90th Percentile	37.0 ppb	21.0 ppb	34.3 ppb	18.3 ppb
	Average	18.1 ppb	10.0 ppb	18.1 ppb	10.0 ppb

Table 12: MECP PM_{2.5} Ambient Air Quality Monitoring Data (2005-2006, and 2016-2017)

Contaminant		2005-06 (24 hour)	2016-17 (24 hour)
PM _{2.5}	Max	41.7 µg/m ³	24.4 µg/m ³
	90th Percentile	17.8 µg/m ³	12.1 µg/m ³
	Average	8.1 µg/m ³	6.9 µg/m ³

Although the results presented in **Tables 11** and **12** are not predictive or representative of the concentrations of air contaminant within the MTSA, they do illustrate a declining concentration of air contaminants since the inception of the CAS. NO_x and PM_{2.5} are generated from a variety of processes, with vehicles and industry being the major contributors. VOCs are also largely emitted from vehicles and industrial processes. In consideration of these findings, undertaking an air quality study (update to CAS) to better understand and characterize the existing ambient air quality in the area is recommended prior to permitting the development of additional sensitive land uses in the area.

4.2 Local Meteorology

Local meteorological data, in the form of wind speed and direction, was gathered from Toronto Island Airport, which was chosen due to its proximity to the study area and the influence of lake effects. Wind speed and direction data for the 2003-2005 period are presented in **Figure 3**. Of note, there is a significant easterly (i.e., blowing from the east) component to local winds, and an even distribution of winds blowing from the northwest through to due south. Considering that the majority of industries considered are south or west of the MTSA, it is expected that winds from the northwest through due south will blow from the industries to the proposed development areas (including proposed residential land uses) with regularity.




Figure 3: Wind Rose for 2003 through 2005 from Toronto Island Airport

4.3 Existing Industries – Air Quality

The industries in proximity to the MTSA were reviewed from a qualitative standpoint. This review includes consideration of the type of operations at each industry, the proximity to the MTSA, and a summary of the potential impacts which may be expected off-site due to each industry, as presented in **Table 13**. The information presented for each industry was obtained from the industry's ECAs, satellite imagery, and engineering knowledge. This review identifies that there are several class 2 and 3 industries in proximity to the MTSA, and that significant emissions with the potential to impact the MTSA may be expected. It can be seen that some facilities include tall stacks and large features (e.g., storage tanks, operations, boilers, etc.) that would have the potential to result in notable air quality impacts. The industries, with their applicable D-6 classifications, are shown in **Appendix B**.

Table 13: Local Industries within the MTSA – Air Quality

Facility Name	Description of Operations and Features	Distance from Development	D-6 Classification	Potential Impacts Air Quality
CRH Canada Group Inc.	<ul style="list-style-type: none"> • Large scale cement and aggregate facility (crushing, processing, handling) • Cement storage; • Transloading; • Large stacks 	<1 km	3	<ul style="list-style-type: none"> • Particulate matter • Dust • Combustion by-products
Tri-Phase Environmental	<ul style="list-style-type: none"> • Aggregate crushing, processing, and handling 	<2 km	2	<ul style="list-style-type: none"> • Particulate matter • Dust • Combustion by-products
Clean Harbors Canada, Inc.	<ul style="list-style-type: none"> • Liquid and sludge waste facility (receiving, handling and processing) • Chemical and waste storage tanks, • Chemical and waste pump trucks • Laboratory fume hoods; and • Aerosol can crushing. 	<1.5 km	2/3	<ul style="list-style-type: none"> • VOCs • Combustion by-products • Odours
Petro-Canada Lubricants	<ul style="list-style-type: none"> • Large petrochemical manufacturing and storage; • Intermediate feedstock refined to produce: <ul style="list-style-type: none"> ○ Lubricants (automotive, industrial and food grade); ○ Greases; ○ Base and process oils; and, ○ Specialty fluids. • Large chemical storage tanks; • Large stacks; • Large boilers; • Transloading; and, • Water and wastewater treatment. 	<1 km	3	<ul style="list-style-type: none"> • VOCs • Combustion by-products • Odours • Particulate matter
Trimac Transportation Services	<ul style="list-style-type: none"> • Transportation and logistics yard; • Truck and tanker handling and storage • Tanker and truck washing; and • Small stacks 	<1.5 km	2	<ul style="list-style-type: none"> • Combustion by-products • Dust

Facility Name	Description of Operations and Features	Distance from Development	D-6 Classification	Potential Impacts Air Quality
H.L Blachford Limited	<ul style="list-style-type: none"> • Manufacturing of chemicals used in the rubber, paint and ink industries; • Products generally include pigments and dyes; • Stacks; • Chemical; and, • Storage tanks. 	<0.3 km	2	<ul style="list-style-type: none"> • VOCs • Combustion by-products • General air contaminants • Odour
IPEX Inc.	<ul style="list-style-type: none"> • PVC manufacturing • Injection moulding and grinding; • Research and development activities; • Stacks; • Chemical storage tanks; and, • Transloading. 	<0.5 km	2	<ul style="list-style-type: none"> • VOCs • Combustion by-products • General air contaminants • Odour
Stackpole Powertrain International ULC	<ul style="list-style-type: none"> • Manufacturing automotive castings for oil and transmission fluid pumps; • Machining aluminum and steel parts; • Parts washing, assembly and testing; and, • Small stacks. 	<0.5 km	2	<ul style="list-style-type: none"> • VOCs • General air contaminants • Combustion by-products
ICS Universal Drum Reconditioning Limited Partnership	<ul style="list-style-type: none"> • Re-conditioning, cleaning, and re-furbishing of steel and plastic drums; • Acid and caustic washing of steel tanks; • Caustic wash of plastic drums; • Acid wash of IBCs; • Drum shredding, crushing; • Drum painting; • Recycled drum services; • Chemical storage tanks; and, • Stacks. 	<1 km	2	<ul style="list-style-type: none"> • VOCs • General air contaminants • Combustion by-products

Facility Name	Description of Operations and Features	Distance from Development	D-6 Classification	Potential Impacts Air Quality
Ashland Canada Corp. and Valvoline Canada Corp.	<ul style="list-style-type: none"> • Chemical and solvent repackaging and blending facility • Receives, stores and distributes chemical products and paint; • Stacks; • Storage tanks; and, • Transloading. 	<1.5 km	2	<ul style="list-style-type: none"> • VOCs • Combustion by-products
2159978 Ontario Limited	<ul style="list-style-type: none"> • Ready-mix concrete facility; • Road salt storage. 	<1.5 km	2	<ul style="list-style-type: none"> • Dust • Particulate matter
Wastewater Treatment Plant - The Regional Municipality of Halton	<ul style="list-style-type: none"> • Municipal wastewater treatment facility servicing the Halton Region • Large wastewater treatment processes 	<3 km	3	<ul style="list-style-type: none"> • Odour
Clarkson Wastewater Treatment Plant	<ul style="list-style-type: none"> • Municipal wastewater treatment facility • Large wastewater treatment processes 	<1.5 km	3	<ul style="list-style-type: none"> • Odour
Mancor Canada Inc.	<ul style="list-style-type: none"> • Carbon steel manufacturing; • Plasma cutting; • Stamping and light machining; • Welding and painting; • Storage tanks; and, • Small stacks. 	<2 km	2	<ul style="list-style-type: none"> • VOCs • Particulate matter • General air contaminants
UBA Inc.	<ul style="list-style-type: none"> • Chemical logistics facility, named as key contributor to the Clarkson airshed. (Air/Noise approvals not found); and, • Storage tanks. 	<1.5 km	2	<ul style="list-style-type: none"> • VOCs • Odours
Musket Transport Inc.	<ul style="list-style-type: none"> • Transportation and logistics yard with truck and tanker handling and storage. <p><i>NOTE: Musket Transportation is within the MTSA, and has not been considered further.</i></p>	<0.3 km	2	<ul style="list-style-type: none"> • Dust • Combustion by-products

4.4 MTSA Plan and Study Considerations

The location of the proposed MTSA as well as the relevant industries identified and assessed as part of this study are presented in **Figure 4**. **Figure 5** shows the MTSA plan with proposed building elevations identified for each sub-section of the proposed land use development.



Figure 4: MTSA (shown in pink) and Industries Considered For this Study



Figure 5: MTSA Plan with Building Heights Represented in each Block

Potential incompatibilities between the MTSA and neighbouring industries are primarily dependant on proximity to the industry and elevation of the development. The following sections provide an outline of potential compatibility issues with respect to nuisance contaminants and regulated air contaminants.

4.4.1 Nuisance Contaminants (Dust and Odour)

Dust and odour are typically assessed at existing discrete sensitive receptor locations. Some of the existing industries were established prior to the development of nearby sensitive receptors, and as such may not have been required to assess dust or odour impacts at the proposed development locations at the time of applying for approval through the MECP. As a result, introducing new sensitive receptors can present the following issues:

1. Regardless of which lands were developed first, industries must demonstrate compliance at all sensitive receptors. This means that an industry which currently is operating in compliance with the provincial regulations can become non-compliant when new sensitive receptors are introduced nearby.

2. Introducing sensitive receptors (i.e., residential land uses) in an area which has not been previously assessed for odour or dust may result in significant complaints from new receptors.

Based on the above, assessments for nuisance contaminants should be performed whenever a new sensitive receptor is proposed which may be affected by a likely source of dust or odour. The D-Series Guidelines provide helpful criteria for determining when an assessment is required in the form of Areas of Influence and Recommended Minimum Setback Distances. Depending on the class of the industry (as shown in **Table 13**) the Area of Influence – within which, encroaching industries should be studied – ranges from 70 m (Class I Industries) to 1000 m (Class III Industries) (see **Figures B1** and **B2** in **Appendix B**). **Figure 6** shows the blocks of the MTSA which are within the minimum area of influence of a suspected source of a nuisance contaminant. These blocks should be studied further prior to approval of any land use changes or further intensification within the MTSA.




Figure 6: Development Blocks where Nuisance Impact Studies are Recommended (shown in purple)

The proposed office buildings to the west of the MTSA are not identified as requiring assessment despite being within the Area of Influence of several industries. Typically office buildings are not considered sensitive receptors. In order to promote compatibility, it is recommended that any institutional/commercial use include non-operable windows and/or appropriate air contaminant control systems as part of their air handling equipment (e.g., carbon filter for odour).

Non-sensitive outdoor locations (e.g., parks, patios) are typically assessed assuming intermittent use and as such may not result in regulatory compliance issues for the nearby industries, however, they should be considered in the assessment for the potential for nuisance complaints.

4.4.2 General Air Contaminants

All regulated air contaminants are required to be assessed by an industry at any point off-site, including areas that are zoned industrial / commercial. These assessments do not include cumulative impacts from other neighbouring industries and do not account for existing ambient concentrations. The exception to this is elevated points of reception where zoning did not previously allow elevated uses. A new sensitive receptor above ground level (e.g., an apartment window or balcony) represents a new point of reception that an industry would need to demonstrate compliance at. As such, any block within the MTSA which is proposing sensitive uses above three-storeys in height (considered “above ground-level”), and which falls within the Area of Influence as per Guideline D-6, should be assessed. An exception to this recommendation would be when the proposed block is in a similar location to an existing sensitive receptor of similar height for which an assessment has already been completed for industrial approval purposes.

Figure 7 shows the blocks where air quality studies are recommended. It is recommended that a detailed air quality study, including dispersion modelling, be performed prior to allowing more sensitive land uses in the area.



Figure 7: Development Blocks where General Air Contaminants should be assessed (shown in purple)

4.5 Recommendations

Potential Air quality impacts can be mitigated through implementation of control technologies at source; however, a feasibility assessment (technical and financial) is typically a prerequisite. The extent

to which a business is able to mitigate its air and odour emissions should be considered to determine the impact of such mitigations.

Mitigation measures or controls are typically specific to sources or type of contaminant emission rather than an industry or a business and are intended to reduce impacts to meet regulatory requirements rather than eliminate them. There are specific standards / guidelines for air quality and odour as well as methodology to assess such impact so that proponents can determine the need for mitigation measures and then proceed with assessing the feasibility of such measures.

Mitigation can also be achieved through implementation of strategies rather than installation of control technologies, such as elimination of a source of emission or changing operations (e.g., reducing operating hours). Mitigation tends to be assessed on a case-by-case basis. **Table 14** provides a list of commonly applied control technologies for air contaminant and odour emission sources.

Table 14: Commonly applied control technologies for air quality and Odour

Impact Type	Impact Specifications	Common Control Measures
Air Quality	Particulate Matter	Dust collectors / baghouses
		Cyclones
		Electrostatic precipitators
		High temperature ceramic particulate filters
	Nitrogen oxides (NO _x)	Selective Catalytic Reduction (SCR)
	Volatile Organic Compounds (VOCs)	Thermal oxidizers (incinerator)
		Adsorptive technology
	Unburnt Hydrocarbons	Catalytic converters
Odour	Stationary odour sources	Carbon monoxide
		Catalytic converters
		Polycyclic Aromatic Hydrocarbons (PAHs)
		Catalytic converters
		Bio filters
		Odour neutralizing compounds

The following recommendations are based on the information gathered and discussed above, related to air quality impact of the existing industrial establishments on the proposed development within the MTSA:

1. Prior to implementing any proposed changes to land use within the study area, any blocks identified in **Figure 6** as requiring an assessment for nuisance contaminants should be subject to a thorough review. The assessment should consider combined impacts from local industries (cumulative effect) and should be based on relevant MECP guidelines and regulations, including O.Reg. 419/05.
2. Prior to implementing any proposed changes to land use within the study area, any blocks identified in **Figure 7** as requiring an assessment for general air contaminants should be subject to a detailed study. The study may include a combination of dispersion modelling assessment of local industries and an updated air quality monitoring program to characterize existing local air quality. A dispersion modelling study should be conducted in accordance with relevant guideline documents and protocols set by MECP. For an updated air quality monitoring program, consideration should be given to duration of the program as well as monitoring locations to ensure representative data is gathered. The assessment should use the MECP's ACB and AAQC for determination of potential impacts. The scope of these assessments should be determined on a case-by-case basis by a qualified air quality engineer. It is recommended that these studies be peer reviewed by independent third party specialists.

For contaminants where the measured ambient levels have historically shown to exceed the relevant standards or criteria (e.g., acrolein, benzene), an air quality based human health risk assessment should be undertaken by a qualified specialist. The scope of the assessment, including relevant guidelines, should be prepared by a qualified human health risk assessor.

3. Given the results of the CAS, irrespective of recommendations 1 and 2, above, it is recommended for the City to consider requiring an air quality based human health risk assessment to be completed for any sensitive land use development within the MTSA, prior to approval.
4. An up-to-date ambient air quality monitoring study, especially for contaminants that had shown levels above the AAQC would allow for better characterization of the existing air quality in the area. The study can then be used by the City as an effective tool in the decision making process related to the planned intensification, while maintaining a factual perspective on future potential human health impacts related to air quality. The duration and monitoring locations are key factors that should be carefully assessed and selected for such a study.

5.0

Noise and Vibration Review

5.1

Noise Impact

Sound is most simply defined as the vibration in the air that we can hear. Vibrating surfaces (such as engines, drums, loudspeakers etc.) typically produce pressure fluctuations in the air. The pressure fluctuations spread out like waves in the air, in all directions, decreasing in intensity with distance from the Source. Our ears sense the pressure fluctuations and create electrical signals that our brain interprets as sound. [3]

Sound has three distinctive characteristics that the ear identifies [4]:

- 1) Amplitude (loudness or softness) – measured in “Decibels”;
- 2) Frequency or “Pitch” – representing a range of “low” to “high” sounding tones; Pitch is determined by frequency of wavelength, measured in cycles per second or “Herz”; and
- 3) Time Patterns (variability) – intermittent sounds versus sounds of longer duration; the concept of “Leq” measures sound over a specific time period.

To mimic the ear’s sensitivity to sound, sound level data at various frequency spectrum are adjusted (weighted) to create values known as “A-weighted”. The resulting sound levels (A-Weighted) are expressed in unit of A-Weighted decibels) or “dBA”.

Sound is considered “Noise” when it is “unwanted” sound. It is usually unwanted because it interferes with human activity or causes an annoyance. Noise levels have increased as urbanization and industrialization have expanded in modern times. Urbanization has concentrated populations in close proximity to each other, and in close proximity to industrialized activities and manufacturing sites. As cities continue to urbanize, the need has arisen to intensify residential housing within existing city limits to curb urban sprawl and promote the efficient use of land and resources. Increased density inevitably brings increased sound levels. The development and expansion of transportation infrastructures (e.g., roads, highways and railways) has resulted in constant transportation related noise.

Human ears can hear a wide range of pressure intensities. The “Decibel” scale was developed to represent the range of audible sounds that human ears can detect in terms of loudness or softness. The Decibel scale represented as “dB” measures the sound pressure level in Decibels. 0 Decibels represents the threshold of hearing. 120-130 Decibels represents the upper end of sound that can be painful or highly uncomfortable. Typical noise sources and their respective sound levels that humans are exposed to regularly are presented in **Figure 8**. Each increase in sound level by approximately 10 dB results in roughly doubling of perception of loudness.




Figure 8: Typical Sources of Noise and Threshold Interference

5.2 Vibration Impact

In general, ground-borne vibration consists of oscillatory waves that propagate from the source through the ground to adjacent buildings. Ground vibration at a receiver location is typically a result of energy propagation through the ground from a source (e.g., industrial facility, rail, blasting) to a receiver by exciting the grounds and creating vibration waves that spread through the soil and rock layers to the foundations of nearby receiver buildings. The vibration can then move from the foundation throughout the rest of the building structure causing windows, walls and objects inside the building to “shake and rattle”.

In contrast to air-borne noise, ground-borne vibration is not a phenomenon that people normally experience every day. While vibration exists all around, it is typically below the threshold of perception for humans. However, ground-borne vibration can be a concern for occupants of buildings in proximity to railway corridors, heavy industries with stamping operation, or mining sites with blasting operation.

Ground-borne vibration is almost never annoying to people who are outdoors. Although the motion of the ground may be perceived, without the effects associated with the shaking of a building, the motion does not provide the same adverse human reaction. The perception of vibration arises inside a building. The vibration of floors and walls may cause feelable vibration, rattling of items such as windows or dishes on shelves, or a rumble noise. The rumble is the noise radiated from the motion of the room surfaces. In essence, the room surfaces act like a giant loudspeaker causing what is called ground-borne noise.

Annoyance from vibration often occurs when the vibration exceeds the threshold of perception by only a small margin. A vibration level that causes annoyance will be well below the damage threshold for normal buildings. Building damage is typically not a concern for development in proximity of industrial / commercial establishment as ground vibration would not exceed 10 mm/sec, Root-Mean Square (RMS), required to cause structural damage. However, the effects of vibration on occupants include fear of damage to the occupied structure and its contents, as well as more direct adverse effects such as distraction, irritation and subsequent interference with quiet activities or sleep patterns. To put all this into perspective, the background vibration velocity level in typical residential areas is usually less than 0.03 mm/sec RMS. This is well below the threshold of perception for humans which is around 0.1 mm/sec RMS. Some typical vibration sources, their associated velocity levels and human/structural responses are presented in **Figure 9**.




Figure 9: Typical Vibration Sources, Levels and Human /Structural Response

5.3 Existing Industries – Noise & Vibration Review

The industries in proximity to the MTSA were reviewed from a qualitative noise and vibration impact perspective. This review includes consideration of the type of operations at each industry, the proximity to the MTSA, and a summary of the potential impacts which may be expected beyond the property boundaries of the facilities, as presented in **Table 15**.

The information presented for each industry was obtained from the ECAs, satellite imagery, and Dillon's experience and engineering knowledge of various industrial processes / operations / activities in relation to noise and vibration emissions.

Table 15: Local Industries within the MTSA

Facility Name	General Facility Description	Distance from Development	D-6 Classification	Potential Impacts Noise & Vibration
CRH Canada Group Inc.	Large scale cement and aggregate facility (crushing, processing, handling)	<1 km	3	Noise Ground Vibration*
Tri-Phase Environmental	Aggregate crushing, processing, and handling	<2 km	2	Noise Ground Vibration*
Clean Harbors Canada, Inc.	Liquid and sludge waste facility (receiving, handling and processing)	<1.5 km	2/3	Noise
Petro-Canada Lubricants	Large petrochemical manufacturing and storage facility for Lubricants	<1 km	3	Noise
Trimac Transportation Services	Transportation and logistics yard with trucks and tankers storage yard	<1.5 km	2	Noise
H.L Blachford Limited	Manufacturing of chemicals used in the rubber, paint and ink industries	<0.3 km	2	Noise
IPEX Inc.	PVC manufacturing and Injection moulding and grinding	<0.5 km	2	Noise
Stackpole Powertrain International ULC	Manufacturing automotive castings for oil and transmission fluid pumps;	<0.5 km	2	Noise
ICS Universal Drum Reconditioning Limited Partnership	Re-conditioning, cleaning, and re-furbishing of steel and plastic drums;	<1 km	2	Noise
Ashland Canada Corp. and Valvoline Canada Corp.	Chemical and solvent repackaging and blending facility	<1.5 km	2	Noise
2159978 Ontario Limited	Ready-mix concrete facility and road salt storage.	<1.5 km	2	Noise
Wastewater Treatment Plant - RMH	Municipal wastewater treatment facility servicing the Halton Region	<3 km	3	Noise
Clarkson Wastewater Treatment Plant	Municipal wastewater treatment facility	<1.5 km	3	Noise

Facility Name	General Facility Description	Distance from Development	D-6 Classification	Potential Impacts Noise & Vibration
Mancor Canada Inc.	Carbon steel manufacturing with plasma cutting, welding, stamping and painting	<2 km	2	Noise Ground Vibration*
UBA Inc.	Chemical logistics facility with transport truck traffic to and from the facility (Air/Noise approvals not found)	<1.5 km	2	Noise
Musket Transport Inc.	Transportation and logistics yard with truck and tanker handling and storage <i>NOTE: Musket Transportation is within the MTSA, and has not been considered further.</i>	<0.3 km	2	Noise

* The ground vibration impact is expected to be localized and not to extend notably beyond the property boundaries of the identified industrial facilities.

5.4 Implications of Noise and Vibration on the Proposed Development Plan

Noise Implications

In addition to review of the available ECAs for the above-mentioned industries, daytime and nighttime site noise surveys were conducted by Dillon as part of this study to better characterize the existing noise environment and potential noise / vibration impact that may be experienced at the proposed sensitive land uses. The area can be classified as Class I – Urban (as per NPC-300):

“An area with an acoustical environment typical of a major population centre, where the background sound level is dominated by the activities of people, usually road traffic, often referred to as “urban hum.”

The noise levels in the area are primarily influenced by vehicular traffic. During daytime hours, truck traffic serving the industrial and commercial establishments in the area notably increases the traffic noise levels while. Rail related activities from a nearby rail yard as well GO Transit trains are audible within the MTSA areas north of Royal Windsor Drive – Lakeshore Road West. Although the railway noise is intermittent and for short durations, it dominates the noise level in the immediate vicinity of the railway and is more pronounced during nighttime hours, when road traffic is reduced.

Industrial noise sources from heavy industries are more audible to the south of Orr Road and beyond the west boundary of the CFRB 1010 antenna installation areas.

From the pool of industrial facilities in the area that were assessed in this study, the CRH Canada large scale cement and aggregate facility would be considered the most impactful from a noise perspective.

The dominant noise sources at this facility are spread from the south end of the property boundary to near the north end (crushing and stockpiling operations and heavy mobile equipment operation). The north property boundary of this facility is approximately 800m from the closest point of the MTSA with absorptive grounds in between. Absorptive grounds help attenuate noise, however, as the receptor elevation increases (i.e., in case of high rises) the effect of ground absorption diminishes. The operations at CRH Canada can be distinctly audible at the southwest end of the shopping plaza at Royal Windsor Drive and Southdown Road as well as at the west end of the ORC – Ontario Racquet Club. As such, the development areas on the southwest quadrant of Royal Windsor Drive and Southdown Road are likely going to be impacted by industrial operations. It is noted that if an industrial facility is audible at a receptor location, it does not necessarily mean that the facility is exceeding the applicable noise level limits, as described in NPC-300.

The dominant stationary noise sources for Petro-Canada Lubricants facility are mainly at the south end of the facility and as such do not cause a notable impact at receptors north of Orr Road. The dominant noise sources at the wastewater treatment plants are not audible north of Orr Road.

Noise emissions from the rest of the industrial establishments that were reviewed as part of this study are related to truck traffic to / from the sites and therefore fall under road traffic noise impact, as discussed above.

Vibration Implications

From the nearby industries, the ground vibration generation is expected from Mancor Canada Inc. (Stamping operation) as well as CRH Canada and Tri-Phase Environmental (crushing and operation of heavy mobile equipment). Ground vibrations generated at these facilities are expected to diminish rapidly with distance and are not expected to extend significantly beyond the property boundaries of these facilities. As such, ground vibration from nearby industrial sources is not considered a concern for the proposed development plan.

Rail operation along the rail corridor is expected to generate ground vibration that can impact areas on either side of the rail corridor. Typically, notable rail-generated ground vibration can extend 75m or 100m beyond the rail right-of-way and also result in ground borne noise, indoors. Type of train, condition of track and wheels, train travel speed and transfer mobility factor of the grounds in between rail and receiver influence the level of vibration that a receptor would experience from rail operations. For the proposed MTSA plan, it is expected that development within 75m of the rail corridor (north and south side) can experience ground vibration impact.

5.5 Recommendations

Many of the environmental impacts can be mitigated through implementation of existing control technologies at source and/or at receptor; however, a feasibility assessment (technical and financial) is typically a prerequisite.

Mitigation measures or controls are typically specific to sources or type of contaminant emission rather than an industry or a business and are intended to reduce impacts to meet regulatory requirements rather than eliminate them. There are specific standards / guidelines in place for noise and vibration as well as methodology to assess such impacts, so that proponents can determine the need for mitigation measures and then proceed with assessing the feasibility of such measures. Mitigation measures can also be implemented at the receptor location, such as installation of a noise barrier wall at a receptor to reduce noise impact, use building construction materials with appropriate Sound Transmission Class (STC) rating to achieve suitable indoor noise levels, and install vibration isolation at building footing to limit / eliminate ground vibration.

Mitigation can also be achieved through implementation of strategies rather than installation of control technologies, such as elimination of a source of emission or a receptor through acquisition. In scenarios where the implementation and/or operation of a control technology is more costly than acquiring a receptor or a business and eliminating it as a receptor or a source, it would be more cost effective to implement such a strategy than to mitigate through the control technology.

Mitigation tends to be assessed on a case-by-case basis. **Table 16** provides a list of commonly applied control technologies for noise and vibration.

Table 16: Commonly applied control technologies for noise and vibration

Impact Type	Impact Specifications	Common Control Measures
Noise	Stationary noise sources	Silencers
		Acoustic Louvers
		Acoustic enclosures
		Noise barrier wall
		Noise berm
Vibration	Stationary vibration sources	Isolation pads / adsorptive pads
		Foundation isolation

Based on the high level qualitative assessment completed for this study, the following recommendations are suggested:

- For developments that are located in the southwest quadrant of Royal Windsor Drive and Southdown Road, a detailed noise impact assessment should be undertaken for each of the proposed residential buildings to ensure that appropriate noise mitigation measures are going to be implemented in the design and construction of the sensitive-receptor buildings such that the applicable noise limits are met.
- For developments within 75m of the rail corridor, a detailed noise and ground vibration assessment should be undertaken to ensure that appropriate noise (including Ground Borne Noise) and vibration mitigation measures are implemented in the design and construction of the sensitive-receptor buildings such that the applicable noise and vibration limits are met.

6.0 Radiofrequency Review

The Bell Media Corporation operates the CFRB 1010 AM radio transmission antenna array on a relatively large parcel of land located south of Royal Windsor Drive, west of Southdown Road. The subject land parcel is adjacent to the proposed mixed used development areas within the MTSA. As part of this review study, a high-level assessment of Radiofrequency (RF) field impact on the proposed development was completed to determine potential RF field strength and determine if mitigation measures are required.

6.1 Analysis and Impacts

The CFRB1010 AM antenna array has a power rating of 50 kW and transmits at centre frequency of 1,010 kHz. The actual locations of the antennas and the power / frequency ratings were used to model the electric field for both daytime and nighttime. The reference level (i.e., standard) for the electric field, based on Health Canada's Standard for human exposure was determined to be at 86.57 V/m. Computer modelling was completed to determine the electric field strength (in Volt per meter, V/m) for the transmitter antenna array for daytime and nighttime. The model-predicted levels for daytime and nighttime are presented in Figures 1 and 2 in **Appendix A**. The results indicate that the electric field strength is well below the human exposure limit of 86.57 V/m.

The AM antennas are designed to generate strong electric fields for audio signal transmission. The magnetic field strength generated by the AM antenna array is considered to be negligible, and would fall well below the Health Canada's human exposure levels, especially at distances of greater than 10m from the antennas. The magnetic field strength is far less than that of the electric field strength and as such, it is not considered in the analysis.

6.2 Mitigation and Recommendation

Although the analysis indicates that the electric field strength for MTSA study areas is less than the Health Canada Standard for human exposure, the same field strength can notably interfere with electronic devices such as radios, clocks, phones and televisions that may be used in the nearby proposed buildings.

Installation of architectural features on building façade, such as conductive interconnected metallic features that are grounded can be used to dissipate the electric field of the transmitted RF at the building façade. Use of grounded wiring to aluminum frame of windows is also an effective way to limit the electric field in the interior space. It is the commendation of this study that a detailed RF assessment and mitigation analysis be undertaken by the developers prior to the design of buildings so that appropriate mitigative measures can be incorporated in the design of the buildings.

Closure

This Report has been prepared based on the information provided by or through The Planning Partnership (TPP), the City of Mississauga and publically available data. This report is intended to provide a reasonable review of available information within an agreed work scope, schedule and budget. This report was prepared by Dillon and its subcontractor, Vitatech Electromagnetics, for the sole benefit of TPP and the City of Mississauga. The material in the report reflects Dillon's judgment in light of the information available to Dillon at the time of this report preparation. Any use which a third party makes of this report, or any reliance on or decisions made based on it, are the responsibilities of such third parties. Dillon and its subcontractor accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this report.

We trust that the report is to your satisfaction. Please do not hesitate to contact the undersigned if you have any further questions on this report.

8.0

References

- Health Canada. 2015. Safety Code 6: Limits of Human Exposure to Radiofrequency Electromagnetic Energy in the Frequency Range from 3 kHz to 300 GHz.
- Ministry of the Environment and Climate Change. 2017. O. Reg. 419/05: Air Pollution - Local Air Quality
- Ministry of the Environment and Climate Change. 2017. Environmental Activity and Sector Registry – Limits and Other Requirements (Version 2, consolidated as of September 2017).
- Ministry of the Environment and Climate Change. 2011. Approval for discharge into the natural environment other than water (i.e., Air) - EPA s. 9.
- Ministry of the Environment and Climate Change. 2013. Environmental noise guideline. Stationary and transportation sources: Approval and planning, Publication NPC-300.
- Ministry of the Environment and Climate Change. 2005. R.R.O. 1990, Reg. 346: General - Air Pollution.
- Ministry of the Environment and Climate Change. 1997. Noise Assessment Criteria in Land Use Planning: Requirements, Procedures and Implementation.
- Ministry of the Environment and Climate Change. 1995. Environmental Land Use Planning Guidelines.
- Ministry of the Environment and Climate Change. 1990. Environmental Protection Act, R.S.O. 1990, c. E.19.
- United States Environmental Protection Agency. 1972. AP-42, Fifth Edition Compilation of Air Pollutant Emission Factors, Volume 1: Stationary Point and Area Sources.

Appendix A

Radio Frequency Analysis

Frequency (MHz)		Reference Level Basis	Reference Level (E _{RL}), *V/m, RMS)		Reference Period
			Uncontrolled Environment	Controlled Environment	
General	0.003 – 10	NA	83	170	Instantaneous
	1.0 – 10	SAR	87/f ^{0.5}	193/f ^{0.5}	6 minutes
1.01	1.01	SAR	86.57	192.04	-






Figure #1

Issue: 1.0

VTE-3172C

Prepared By: JPH

Date: 11/01/2019

CBRF Toronto AM Antenna

Dillion Consulting Limited

Daytime Electric Field Strength

Tranmitter	Frequency	Field Elevation
CFRB Tononto	1,010 kHz	Ground

Levels from CFRB Toronto, ON - Daytime Plot

Extrapolated Electric Field Strength Levels based on Linear Decay

Frequency (MHz)		Reference Level Basis	Reference Level (E _{RL}), *V/m, RMS		Reference Period
			Uncontrolled Environment	Controlled Environment	
General	0.003 – 10	NA	83	170	Instantaneous
	1.0 – 10	SAR	87/f ^{0.5}	193/f ^{0.5}	6 minutes
1.01	1.01	SAR	86.57	192.04	-



Figure #2		CBRF Toronto AM Antenna		
Issue: 1.0		Dillion Consulting Limited		
VTE-3172C		Nighttime Electric Field Strength		
Prepared By	Date	Transmitter	Frequency	Field Elevation
JPH	11/01/2019	CFRB Toronto	1,010 kHz	Ground

_____ Levels from CFRB Toronto, ON - Night time Plot

_____ Extrapolated Electric Field Strength Levels based on Linear Decay

Appendix B

Guideline D-6 Industrial Classification




Figure B1:
Areas of influence
of Class 2 Industrial
Facilities

Legend

- Industrial Facility
- 70m Recommended Minimum Separation Distance
- 300m Area of Influence



CREATED BY: Adam Boyce
 CHECKED BY: Aron Trauern
 DESIGNED BY: Aron Trauern
 Map Location:
 \\atlanta\dillon_2015\Projects\Toronto CAD\GRAPHICS -
 Planning_P\Projects\18-1227 Clarkson Industrial Overview
 PROJECT: 18-1227 STATUS: FINAL DATE: 10/16/19




Figure B2:
Areas of influence
of Class 3 Industrial
Facilities

Legend

- Industrial Facility
- 300m Recommended Minimum Separation Distance
- 1000m Area of Influence



CREATED BY: Adam Boyer
 CHECKED BY: Aron Trauern
 DESIGNED BY: Aron Trauern
 File Location:
 \\atlanta.dillon_dp5\Projects\Projects CAD\GRAPHICS -
 Planning_P\Projects\11-1227 Clackton Industrial Overview

PROJECT 11-1227	STATUS FINAL	DATE 10/16/19
--------------------	-----------------	------------------



Addendum

To: Romas Juknevičius, M.PL., RPP – City of Mississauga
Taral Shukla, MCIP, RPP – City of Mississauga
Wai Ying Di Giorgio, BLA, OALA – The Planning Partnership

From: Amir Iravani – Dillon Consulting Limited
Hamish Hains – Dillon Consulting Limited

Date: March 10, 2020

Subject: Addendum – Summary of CASIA Ambient Air Monitoring and Recent Air Quality Trends

Our File: 19-1221

This is an addendum to the *Clarkson Air Quality, Noise & Vibration and Radiofrequency Compatibility Overview Study* report (Clarkson Main Report) (Dillon Consulting Limited – January 2020). The purpose of this addendum is to provide an update to the air quality section of the Clarkson Main Report based on the more recent ambient air quality reports that were provided by the Clarkson Airshed Industrial Association (CASIA) for the 2012 to 2018 calendar years (inclusively).

CASIA is an industrial partnership located in the Clarkson area that undertakes regular air quality monitoring in response to the Clarkson Airshed Study (CAS) completed by the Ministry of the Environment, Conservation and Parks (MECP) (formerly MOE) in 2006.

Review of CASIA Reports

CASIA maintains an air monitoring network within the Clarkson airshed. The CASIA air monitoring network is comprised of the following three monitoring stations:

1. STN44086 – Deer Run: monitors PM_{2.5} and NO_x (as NO₂)
2. STN46118 – Meadow Wood Park: monitors PM_{2.5}, NO_x (as NO₂), CO, and O₃
3. STN44666 – PCLI Admin: meteorology station

The list of air contaminants monitored at each station is also indicated above.

This addendum discusses updated results from these stations for NO₂ and PM_{2.5}. Results for NO₂ are compared against Ontario's Ambient Air Quality Criteria (AAQC), while PM_{2.5} is compared against the Canadian Ambient Air Quality standards (CAAQS). For the purposes of this report, conservatively, the maximum concentrations of common air contaminants between the two stations are presented. Dust, odour, volatile organic compounds (VOCs), and speciated VOCs are not monitored by the CASIA air network.

Nitrogen Dioxide - NO₂

Results from the CASIA monitoring reports does not indicate a significant change in either the 98th percentile of the 24-hour average concentration or the maximum hourly concentration of NO₂ between

2012 and 2018. However, the maximum 1-hour and 98th percentile of the 24-hour average concentrations of NO₂ decreased from the 2003-2005 CAS concentrations. Results from both CASIA and CAS for the maximum 1-hour and 98th percentile of the 24-hour average concentrations of NO₂ are well below the 2020 AAQC. A summary of the CASIA NO₂ monitoring results in comparison to the CAS NO₂ monitoring results is provided **Table 1**.

Table 1. NO₂ CASIA and CAS Results Summary Table

Pollutant	Statistical Form	2020 AAQC (ppb)	CAS	CASIA					
			2003-2005 (ppb)	2012 (ppb)	2013 (ppb)	2014 (ppb)	2016 (ppb)	2017 (ppb)	2018 (ppb)
NO ₂	98 th percentile of the 24-hour average concentrations	100	40	19.8	24.3	27.0	19.3	19.3	18.0
NO ₂	Maximum 1-hour concentrations	200	134	65.0	56.0	80.0	65.0	52.0	51.0

Particulate Matter (fine fraction) - PM_{2.5}

CASIA monitoring results indicate a decrease in the 3-year average of the 98th percentile daily concentrations of PM_{2.5} from 2015 to 2018. Both CAS and CASIA data show that the 3-year average of the annual 98th percentile daily concentrations of PM_{2.5} were at or below the CAAQS 2020 standard of 27 µg/m³. A summary of the results is provided in **Table 2**.

Table 2. PM_{2.5} CASIA and CAS Results Summary Table

Pollutant	Statistical Form	2020 CAAQS (µg/m ³)	CAS	CASIA				
			2003-2005 (ppb)	2014 (µg/m ³)	2015 (µg/m ³)	2016 (µg/m ³)	2017 (µg/m ³)	2018 (µg/m ³)
PM _{2.5}	3-yr average of the annual 98 th percentile of the daily 24-hour average concentrations	27	27	27	27	25	23	22

Summary and Closure

The CASIA monitoring results indicate that there have been decreases in NO₂ and PM_{2.5} concentrations between 2014 and 2018. Measured concentrations of NO₂ remain below the Ontario AAQCs. The three year average annual 98th percentile daily concentration of PM_{2.5} has been measured to exceed the CAAQS for 2014/15 and less than the standard for 2016 - 2018. It is noted that the exceedances of PM_{2.5} concentrations is not unique to the Clarkson Airshed. In fact, the PM_{2.5} ambient concentrations occasionally exceed the CAAQS in much of Southwestern Ontario.

CASIA does not monitor for VOCs and as such no results are presented for VOC concentrations in the Clarkson area. In the absence of more recent VOC monitoring data, the conclusions provided in the Clarkson Main Report (based on historical data from the CAS) remain the same.

Terms of Reference (ToR)

Clarkson TSA Air Quality Study

The City of Mississauga is developing land use policies for the TSA to support intensification of the area. It is recognized that with possible redevelopment of this area and introduction of new sensitive land uses, there would be a need to assess air quality impacts on proposed new sensitive developments, especially given the historical state of air quality in the area. The air quality studies are intended to be used to assess the compatibility of proposed development blocks within the TSA. The ToR is prepared by taking into consideration the state of the historic air quality in the area and relevant air quality guidelines and reference documents, including:

This assessment is required to consider the possible introduction of sensitive land uses within the Southdown Employment area of the Clarkson TSA.

- The Environmental Protection Act R.S.O. 1990 Chapter E19;
- Ministry of the Environment, Conservation and Parks (MECP) Regulation 419/05 - Local Air Quality;
- MECP D-Series of Guidelines for Land Use Compatibility;
- Ontario's Ambient Air Quality Criteria (AAQC); and,
- The Clarkson Airshed Study¹ and updated Clarkson ambient monitoring reports (2012 – 2018) prepared by Clarkson Airshed Industrial Association (CASIA).

Follow-up air quality monitoring was recommended in the original Clarkson Airshed Study¹ undertaken by the Province. At the conclusion of the monitoring study, benzene, dichloromethane, and acrolein were identified as air contaminants that exceeded their respective Ambient Air Quality Criteria (AAQCs). Since the conclusion of the Clarkson Airshed Study, there has been a general improvement in the air quality of the region², however, there is no sufficient monitoring data to conclude that benzene, dichloromethane, or acrolein are currently below acceptable levels. This Terms of Reference is divided into two parts: Air Quality Monitoring and Dispersion Modelling, both of which are intended to help better characterize the status of air quality in the area. It is the intension of the City to rely on the findings of such studies to guide their decision making and approval process for the proposed intensification within the Clarkson TSA, including the introduction of sensitive land uses such as: schools, daycares, places of worship, healthcare facilities and residential land uses.

Ambient Air Quality Monitoring Program

Ambient air quality monitoring should be performed in accordance with the Ontario Ministry of the Environment, Conservation and Parks (MECP) *Operations Manual for Air Quality Monitoring in Ontario* (the Manual). The following outlines the recommendations for the Clarkson Ambient Air Quality Monitoring Program:

- The air monitoring system should be sited as per the recommendations of the Manual, in consideration of the specific requirements for particulate matter, sulphur dioxide, nitrogen

¹ Clarkson Airshed Study - A Scientific Approach to Improving Air Quality – Updated 2009

oxides, and VOCs (specifically: benzene, dichloromethane, and acrolein). The air monitoring system should be located in the southern portion of the Clarkson TSA such that the conditions of the Manual (e.g., setback distances from emission sources) can be achieved. The optimal location for the monitoring would be in the southwest quadrant of the intersection of Southdown Road and Royal Windsor Drive. Variation from this proposed siting, or from the Manual, should be reviewed and approved by the City prior to installation of monitors.

- Monitoring should be conducted for nitrogen oxides, total suspended particulate matter (TSP), sulphur dioxide (SO₂), benzene, dichloromethane, and acrolein. Monitoring should be conducted such that each contaminant can be compared against the relevant AAQC statistical averaging periods (i.e., hourly, daily, and annual averages and percentile values).
- Sampling equipment should be selected in consideration of the contaminants being measured and the requirements of the Manual. The Manual provides several equipment options for each air contaminants.
- Monitoring should be conducted for a minimum of six months, and should include the summer period
- Data collection should be conducted following the frequency outlined in the Manual for both continuous (e.g., NO_x) and non-continuous (e.g., PM and VOCs) sampling.

Based on the surface area of the Clarkson TSA and sources of air contaminants in the area, the results from the ambient air monitoring program will generally be representative of the entire study area. As such, execution of separate ambient air monitoring programs may not be required for each individual development within the study area, however, information gathered from ambient air quality monitoring may need to be updated from time to time to better characterize the state of air quality in the area.

Results of the monitoring study are to be compared against Ontario's AAQC, for the relevant averaging periods, using appropriate statistical analysis (see AAQC). The results of the ambient air monitoring study is considered to be representative of ambient air quality concentrations within the Clarkson TSA.

² Clarkson Air Quality, Noise & Vibration and Radiofrequency Compatibility Overview Study, Dillon Consulting, 2019

Dispersion Modelling Study

For each proposed development block (See **Figure 1**), a dispersion modelling study is to be performed to assess air quality at that specific block. Significant sources may include both industrial and transportation sources. The significant sources will change based on the development block being considered as determined by a licensed professional and to the satisfaction of the City.



Figure 1 – Proposed Development Blocks – Clarkson TSA

Industries within the study area should be classified and assessed as per the MECP's D-Series of Guidelines. Where the proposed development is within the Potential Area of Influence of an industry, an assessment of compatibility should be performed, which is to include dispersion modelling as applicable.

The potential air quality impacts of major roadways and/or railways within 500 m of the proposed development should be considered for inclusion in the dispersion modelling study, as applicable. Determination of the requirements for a dispersion modelling study for transportation-related sources (e.g., road and rail) should be determined by a licensed professional and confirmed by the City.

Dispersion modelling should be conducted in accordance with the MECP's "Guideline A-11 Air Dispersion Modelling Guideline for Ontario", including the following project-specific considerations:

- Consideration should be given to large sources in proximity to Lake Ontario. Any active source

exceeding 50 m in height within 1 kilometre of the lake should be assessed with an appropriate shoreline fumigation model. Examples of shoreline fumigation models include, SCREEN3, CALPUFF, and Shoreline Dispersion Model (SDM).

- The dispersion modelling study should consider the built forms of each development in the final build- out of the Clarkson TSA when determining the impact of building effects. Where no built form has been established, consideration should be given to general building massing when performing the modelling and maximum building heights as per the preferred concept plan.
- All elevated points of reception (e.g., balconies, windows, air handling units) should be included as discrete receptor points within the dispersion modelling.

The results of the dispersion modelling should be combined with the results of the ambient air monitoring study to determine the predicted cumulative concentrations of each contaminant, where applicable (Note: this would be the case for a scenario in which contribution of an air contaminant source is not accounted for in the ambient air monitoring data). For contaminants which are not included in the monitoring study, ambient concentration data should be obtained from the relevant MECP or Environment and Climate Change Canada monitoring station. The 90th percentiles of ambient concentrations are to be used to provide a conservative measure of the background concentrations. The cumulative concentration (i.e., modelled concentration + 90th percentile background) should be summarized using the appropriate statistical method and compared to the AAQC.

If the cumulative concentration of a contaminant is below the relevant AAQC, it can be concluded that air quality is likely to be acceptable for that contaminant. Should the cumulative concentration of all contaminants be below the relevant AAQCs, and the compatibility assessment show that land uses are compatible as per the MECP's Guideline D-6, no further action would be required. Should the cumulative concentration of a contaminant exceed the relevant AAQC, further consideration is required. In such situations the frequency and magnitude of the exceedances is to be quantified and the results be reviewed by a qualified human-health risk assessment expert in order to determine appropriate implications and consideration of any mitigation measures for the proposed development / intensification. The results and analysis of the air quality studies are to be peer reviewed by a licensed professional representing the City of Mississauga and review comments / deficiencies are to be addressed prior to issuance of the studies for City's decision making and approval process.

City of Mississauga

Corporate Report



<p>Date: May 25, 2020</p> <p>To: Mayor and Members of Council</p> <p>From: Geoff Wright, P.Eng, MBA, Commissioner of Transportation and Works</p>	<p>Originator's files:</p> <hr/> <p>Meeting date: June 17, 2020</p>
---	---

Subject

Kipling Bus Terminal – Bus Access, Operations and Maintenance Agreement

Recommendation

That a By-law be enacted to authorize the Commissioner of Transportation and Works and the City Clerk to execute on behalf of The Corporation of the City of Mississauga, the Bus Access, Operations and Maintenance Agreement with Metrolinx and any amendments and/or ancillary documents thereto, for the access, operations and maintenance of the Kipling Bus Terminal, all in a form satisfactory to the City Solicitor.

Report Highlights


- In alignment with direction from *The Big Move* (2008), Metrolinx initiated the detailed design and construction of the Kipling Bus Terminal in 2018.
- Substantial completion is planned for fall 2020 with the intent for MiWay to shift services from Islington Station to the Kipling Bus Terminal at the end of 2020 or early 2021.
- As Metrolinx is the owner and operator of the Kipling Bus Terminal and as MiWay will have the right to utilize the terminal and its facilities for its transit related purposes, the City of Mississauga (the "City") and Metrolinx are required to enter into an agreement setting out the terms of use, operations and maintenance responsibilities and cost sharing obligations.
- The Bus Access, Operations and Maintenance Agreement has been prepared by City staff and Metrolinx, and this new Agreement will replace the existing *Kipling Station Redevelopment Memorandum of Understanding* signed on March 7, 2017 and as amended on March 21, 2018.
- City staff, in cooperation with Metrolinx, is recommending endorsement and execution of this Bus Access, Operations and Maintenance Agreement upon finalization of Agreement schedules and details.

Background

Since the inauguration of MiWay, formerly Mississauga Transit, Islington Station has played an important role in connecting the City of Mississauga to the City of Toronto via public transit. With the Toronto Transit Commission's (TTC) east-west subway line terminating at Islington Station until 1980, Islington Station was the obvious east end terminus point for many MiWay routes. However, once the TTC extended its east-west subway line one station further west to Kipling Station in November 1980, numerous discussions were initiated to determine the feasibility of moving MiWay's routes from Islington Station to Kipling Station. It was quickly realized that in order for this to be achieved, a new bus terminal would be required to accommodate all of MiWay's routes at Kipling Station.

In 2008, Metrolinx adopted its first Regional Transportation Plan, *The Big Move*. It provided a vision, goals and objectives for the future of transportation within the Greater Toronto and Hamilton Area (GTHA) and included strategic direction/actions for the implementation of key elements. The creation of a system of connected mobility hubs was one of ten priority actions identified to ensure connectivity between different modes and systems, to support varying and multiple land forms/uses and to enhance the customer experience. In addition to identifying 49 mobility hubs within the GTHA, *The Big Move* also included policies and specific actions to support the development of these mobility hubs. Kipling Station, also referred to as Etobicoke Centre, was identified as one of the 49 mobility hubs in *The Big Move*.

Following recommendations from *The Big Move*, Metrolinx undertook the Kipling Mobility Hub Design Concept Development Study in 2009-2010 and developed a design concept for the bus terminal. However, changing restrictions from Hydro One, a key landowner at the Kipling Mobility Hub, required that a new design be created to address requirements related to safety, maintenance and accessibility. In 2015, Metrolinx completed the Kipling Bus Terminal Feasibility Study which developed a new plan that incorporated key features such as: the bus terminal, bus access, pedestrian access, cyclist access, place-making, passenger pick-up/drop-off (PPUDO) and taxis, commuter parking, development potential, and subway extension as shown in **Figure 1**.

Figure 1. Preferred Station Area Plan (Preliminary Design)

Source: Kipling Bus Terminal Feasibility Study (2015)

The timing for this design was most appropriate as MiWay was experiencing numerous challenges at Islington Station. Some of these challenges included:

- Insufficient platforms and layover spaces;
- Constrained spaces for operational movements;
- Lack of accessible features at the station;
- Inadequate customer and staff amenities; and
- Ongoing infrastructure issues (e.g., structural, pavement, etc.) resulting in operational disruptions related to closures of bays, platforms or the terminal itself.


The development of a new bus terminal at Kipling Station would allow for MiWay services to relocate to a terminal closer to the City of Mississauga/City of Toronto border, provide better connections with TTC and GO Transit, and allow for the redevelopment of Islington Station.

Subsequent to the completion of the feasibility study, a partnership was formed between Metrolinx, the TTC, the City of Toronto, and the City to continue with the detailed design and construction of the new Kipling Bus Terminal. The parties entered into a binding Memorandum of Understanding (MOU) for the Kipling Station Redevelopment dated March 2, 2017, and as amended on March 21, 2018, which identified funding obligations, land conveyances to Metrolinx, allocation of responsibilities for the design and construction processes, and noted

conditions precedent in favour of Metrolinx. Metrolinx was responsible for overseeing the design and construction of the Kipling Bus Terminal with the City committing \$5.5M in funds for the project. The MOU also noted that MiWay could continue to operate out of Islington Station until the completion of the Kipling Bus Terminal through an amended licence agreement, unless the conditions of the platforms became unsuitable or unsafe.

The RFP for the work was issued in 2017 and the successful proponent, EllisDon, initiated the detailed design in 2018 based on a revised site plan, as shown in **Figure 2**.

Figure 2. Kipling Bus Terminal Site Plan



Source: Regional Express Rail: Kipling Station Project Update (2017)

Key elements to the Kipling Bus Terminal include the following:

- Bus access to the terminal via Subway Crescent for MiWay and GO Transit buses;
- A 14-bay/platform terminal with a covered terminal building, of which 10 are dedicated for MiWay's exclusive use;
- A main entry building for walk-in customers;
- Surface features including pedestrian and cycle routes and a redesigned PPUDO and commuter parking lot;
- A pedestrian bridge connecting the main entry building and the terminal building with the GO rail platforms;
- A tunnel from the main entry building to the terminal building and a tunnel from the terminal building to TTC's Kipling subway station;

- Washrooms, transit control room and lounge area assigned for exclusive use by MiWay; and
- Customer amenities including washrooms, waiting area with seating, charging stations and digital schedules within the terminal building and also at each of the bus platforms.

Artist's renderings of the Kipling Bus Terminal are shown in **Figures 3 and 4** for reference purposes only.

Figure 3. Kipling Bus Terminal Rendering: South east view of the terminal



Source: Kipling Design Brief (2018)

Figure 4. Kipling Bus Terminal Rendering: Customer waiting area



Source: Kipling Design Brief (2018)

Present Status

The Kipling Bus Terminal is currently under construction. Metrolinx is targeting a hand over of the terminal late summer 2020, at which time City staff will be able to enter to fit out the terminal for operational readiness. Photos of the construction site have been included for reference purposes in **Figure 5**.

Figure 5. Kipling Bus Terminal Construction Status (May 2020)



Main entry building and pedestrian bridge
(west view)



Terminal building (east view)

Pending delays in the construction schedule, MiWay will shift bus operations from TTC's Islington Station to the new Kipling Bus Terminal at the end of 2020 or early 2021. It is also of note that the City's existing licence agreement with TTC for the use of Islington Station has been extended to December 31, 2020. Any further extension of the agreement beyond this date will result in operational impacts as TTC will need to undertake major rehabilitation work at the station to maintain safe operations.

Comments

As set out in the MOU, Metrolinx is the owner and operator of the Kipling Bus Terminal with MiWay having the right to utilize the terminal and facilities for its transit related purposes. Prior to the commencement of operations at the Kipling Bus Terminal, the City and Metrolinx are required to enter into an agreement setting out the terms of use, operations and maintenance responsibilities and cost sharing obligations. The City and Metrolinx have been cooperating in the preparation of a Bus Access, Operations and Maintenance Agreement and the highlights of the agreement are noted below.

Term of Agreement:

MiWay shall be provided with the exclusive use of 10 platforms, 6 layover spaces, and MiWay-designated areas for the duration of the agreement, as shown in **Appendix 1**, that is, until the Kipling Bus Terminal is fully abandoned. The agreement will be reviewed every 5 years and any termination of the agreement will need to be agreed upon by both parties.

Council	2020/05/25	7
---------	------------	---

Operating and Maintenance Responsibilities:

Metrolinx agrees to perform Operating and Maintenance activities at the Kipling Bus Terminal and its related infrastructure regardless of user designation. These activities include maintenance and minor repairs associated with day-to-day use and will include elements such as garbage pick-up, snow removal, cleaning of buildings, pavement repairs (e.g. cracking, pot holes etc.).

Metrolinx also agrees to perform Capital Maintenance and Rehabilitation Work in order to ensure that the Kipling Bus Terminal is maintained in a good and proper condition. These include elements not considered as Operating and Maintenance work such as replacement and reconstruction activities (e.g. major repairs or replacing of the building and structures).

Financial Impact

Under the Bus Access, Operations and Maintenance Agreement, as of the date that MiWay commences operations at the Kipling Bus Terminal, the City will be responsible for 75% of all Operating and Maintenance costs at the Kipling Bus Terminal or as further defined in the Agreement based on specific uses, with Metrolinx covering the remaining 25%. Metrolinx is responsible for 100% of all capital maintenance and rehabilitation work costs.

While firm costs are not available, based on preliminary high-level estimates, staff believes there should be no material impact to the City's annual operating budget as the operating budget that currently pays for the use of Islington Station should be sufficient to cover costs associated with the use of the Kipling Bus Terminal. The City currently has a budget of \$439,000 (715405-23509) in 2020 of which \$421,712 is for the Islington Station licence fee. This budget will be transferred to the Kipling Bus Terminal lease once the Islington Station lease is terminated. Should there be a significant variation in actual billing from the assigned budget, a budget adjustment will be required in subsequent years.

As the Kipling Bus Terminal is closer in distance to the City's eastern boundary with the City of Toronto, there may also be the opportunity to use resources more efficiently and provide better service through enhanced productivity and improved service reliability.

Conclusion

The construction of the Kipling Bus Terminal will be completed in the second half of 2020 and MiWay will be shifting bus operations from TTC's Islington Station to the Kipling Bus Terminal. To commence operations at the Kipling Bus Terminal, the City and Metrolinx wish to enter into a Bus Access, Operations and Maintenance Agreement. This Agreement has been prepared by City staff and Metrolinx to set out the specific terms and conditions related to the use and responsibilities by both parties and the cost-sharing arrangements. This new Agreement will replace the existing *Kipling Station Redevelopment Memorandum of Understanding* signed on March 7, 2017 and as amended on March 21, 2018. City staff, in cooperation with Metrolinx, is

recommending endorsement and execution of this Bus Access, Operations and Maintenance Agreement upon finalization of Agreement schedules and details.


Attachments

Appendix 1: Kipling Bus Terminal – MiWay Designated Areas



Geoff Wright, P.Eng, MBA, Commissioner of Transportation and Works

Prepared by: Alice Ho, M.A.Sc., P.Eng., Project Leader Transit Priority








METRIC
ALL DIMENSIONS SHOWN ARE IN
METRES AND/OR MILLIMETRES
UNLESS OTHERWISE NOTED








1 OVERALL PLAN
1 : 250

NOTE: ALL EXISTING CONDITIONS
MUST BE VERIFIED ON SITE

REFERENCE DRAWINGS			ISSUE			REVISIONS			DRAWN BY: A. CHAU	DESIGNED BY: S. STRASMAN	 Ontario Association of Architects Sept. 05, 2019 OF ARCHITECTS	 EllisDon INFRASTRUCTURE FINANCER 6000 SHEPPARD AVE. E. SUITE 200, SCARBOROUGH, ONTARIO M1S 1T6 TEL: (416) 291-1100 FAX: (416) 291-1101	 Sai Strasman Architects Inc.	 Metrolinx An Agency of the Government of Ontario	KIPLING GO STATION NEW BUS TERMINAL AND STATION IMPROVEMENTS BUS TERMINAL BUILDING - LEVEL 1 OVERALL PLAN			
									CHECKED BY: S. PURI	APPROVED BY: S. STRASMAN					CONTRACT NO. RFP#16-551	DWG. NO. A-120	REV. 2	SHEET
									SCALE: 1:250						FULL SIZE ONLY			
DWG. NO.	TITLE	NO.	DATE	1.	19/04/05	S-122 IFC - WORKS EXCL. 9158219 KIPLING AV.	2.	19/06/14	REVISED AND RESUBMITTED	3.	19/06/14	REVISED AND RESUBMITTED						
						ISSUED FOR	REV	DATE	DESCRIPTION									



REFERENCE DRAWINGS		ISSUE		REVISIONS		DRAWN BY: L.L./H.L. 19/06/14	DESIGNED BY: L.L./R.N. 19/06/14		 1004 Milliken Rd., Suite 1000 Mississauga, Ontario L4Y 1M4 T: 905-880-8800 F: 905-880-8811 E: ellisdon.com		Kipling Bus Terminal		
						CHECKED BY: R.N. 19/06/14	APPROVED BY: R.N. 19/06/14					 431 Burnellville Avenue, Toronto, ON M6E 2N1 Canada T: 416-340-8700 F: 416-340-7100 HAKO@CHARTERTRUCKS.COM	
DWG NO.	TITLE	1. NO.	19/04/05 DATE	S-122 IFC - WORKS EXCL. 915&919 KIPLING AVE. ISSUED FOR	REV. DATE	19/09/06 REVISED AND RESUBMITTED	19/06/14 REVISED AND RESUBMITTED						
						SCALE: 1:500	FULL SIZE ONLY						